

**CNG Producing
Company**

A CNG COMPANY

CNG Tower
1450 Poydras Street
New Orleans, LA 70112-6000
(504) 593-7000

April 22, 1994

Mr. Ed Forsman
U.S. Dept. of the Interior
Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, UT 84078

RE: River Bend Unit
Application for Permit To Drill
RBU 8-11F - Sec. 11-T10S-R20E

Dear Ed:

Enclosed please find an original and two copies of the above referenced applications. Attachment to this application includes the following:

Attachment No. 1	Location
Attachment No. 2	Certification Statement
Attachment No. 3	BOP Stack Schematic
Attachment No. 4	Drilling Plan
Attachment No. 5	13 Point Surface Use Plan
Attachment No. 6	Water Source and Access Route

CNG Producing Company is requesting all information be held confidential.


Should you have any question please feel free to contact either myself at (504) 593-7260 or the project engineer, David Linger at (504) 593-7779.

Sincerely,

Susan H. Sachitana
Susan H. Sachitana
Regulatory Specialist

Enclosure

cc: Utah Board of Oil, Gas & Mining



UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK
DRILL ☒ DEEPEN ☐ PLUG BACK ☐
b. TYPE OF WELL
OIL WELL ☐ GAS WELL ☒ OTHER ☐ SINGLE ZONE ☐ MULTIPLE ZONE ☐

2. NAME OF OPERATOR
CNG PRODUCING COMPANY

3. ADDRESS OF OPERATOR
CNG Tower, 1450 Poydras St., New Orleans, LA 70112-6000

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)*
At surface 500' FEL & 1,800' FNL of Sec. 11-T10S-R20E

At proposed prod. zone
Same

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR VILLAGE
10 Miles SW of Ouray

15. DISTANCE FROM PROPOSED*
LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.
(Also to nearest drlg. unit line if any) 500'

18. DISTANCE FROM PROPOSED LOCATION*
TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, 1,508'

21. ELEVATIONS (Show whether DF, RT, GR, etc.)
5,043' GR

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH
12 1/4"	8 5/8"	24#	+/- 350
7 7/8"	5 1/2"	17#	+/- 7,300

1. Drill a 12 1/4" hole with an air rig to +/- 350', run 8 5/8", H-40 casing and cement to surface.
2. NU and pressure test BOP stack prior to drilling out below surface pipe.
3. Operate pipe rams daily and blind rams as possible.
4. Drill a 7 7/8" hole to 7,300' with a salt water mud system. Coring is possible. DST's will be run as needed to evaluate unexpected shows.
5. Run logs, set 5 1/2", 17#, N 80 & K-55 casing as dictated by drilling shows, tests, and logs. Casing program may be modified to provide added burst strength if needed for frac program.
6. Primary zones of interest are the Wasatch, Chapita Wells & Ute land Buttes.
7. All zones indicating potential for economically recoverable reserves will be tested in a normal, prudent manner.
8. In the event of lost circulation, air or air assisted mud will be utilized.

FORMATION TOPS	DEPTHS
Wasatch	4,750'
Chapita Wells	5,460'
Ute land Buttes	6,450'

CNG Producing respectfully request that all information concerning this well be held confidential.

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true verticle depth. Give blowout preventer program, if any.

24. SIGNED David L. Linger

(This space for Federal or State office use)

PERMIT NO. 43-047-32512

APPROVED BY _____

CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY THE STATE
TITLE Senior Drilling Engineer DIVISION OF 4/21/94
OIL, GAS, AND MINING

DATE: 6-3-94

BY: John D. Hays

TITLE WELL SPACING: 1647-2-3

*See Instructions On Reverse Side

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FOR APPROVED
BUDGET BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well
☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator
CNG PRODUCING COMPANY

3. Address and Telephone No.
CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
Surface 500' FEL & 1,800' FNL of Sec. 11-T10S-R20E

CONFIDENTIAL

5. Lease Designation and Serial No.
U-01790

6. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation
River Bend Unit

8. Well Name and No.
8-11F

9. API Well No.

10. Field and Pool, or Exploratory Area
Island

11. County or Parish, State
Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent

☒ Subsequent Report

☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment

☐ Recompletion

☐ Plugging Back

☐ Casing Repair

☐ Altering Casing

☒ Other - Variance
in casing

☐ Change of Plans

☐ New Construction

☐ Non-Routine Fracturing

☐ Water Shut-Off

☐ Conversion to Injection

☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

Under Onshore Order #2, casing and cementing requirements, it states " All casing, except the conductor casing, shall be new or reconditioned and tested used casing that meets or exceeds API standards for new casing" the 8 5/8" 24# H-40 surface casing designed for this well and other wells in the River Bend Unit meets all of the above criteria for the order. The 8 5/8" casing is a limited service pipe which means it does not meet API standards. However, the pipe is new and was Hydro statically tested to 2,700 PSI which equals API standards for 8 5/8" 24# K-55 casing.

We respectfully submit this sundry and attached letter from the company the pipe was purchased from.

If any additional information is needed, please advise.

CONFIDENTIAL

14. I hereby certify that the forgoing is true and correct

Signed

David L. Linger
David L. Linger

Title

Senior Drilling Engineer

Date

April 21, 1994

(This space for Federal or State office use)

Approved by

Title

Conditions of approval, if any:

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING

DATE: 6-3-94

BY: *[Signature]*


WELL SPACING: 1647-2-3

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make any statement or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

**CNG PRODUCING CO.
WELL LOCATION PLAT
RBU 8-11F**

LOCATED IN THE SE $\frac{1}{4}$ OF THE NE $\frac{1}{4}$ OF
SECTION 11, T10S, R20E, S.L.B.&M.




SCALE: 1" = 1000'

LEGEND & NOTES

- ◆ Original corner monuments found and used by this survey.

The General Land Office (G.L.O.) plat was used for reference and calculations, as was the U.S.G.S. quadrangle map.



7 Apr '94

79-128-287

SURVEYOR'S CERTIFICATE

I HEREBY CERTIFY THAT THIS PLAT WAS PREPARED FROM FIELD NOTES OF AN ACTUAL SURVEY PERFORMED BY ME, DURING WHICH THE SHOWN MONUMENTS WERE FOUND OR ESTABLISHED.


Jerry D. Allred
JERRY D. ALLRED, REGISTERED LAND SURVEYOR, CERT. NO. 148951 (UTAH)




JERRY D. ALLRED & ASSOCIATES
Surveying & Engineering Consultants

121 North Center Street
P.O. Box 975
Duchesne, UTAH 84021
(801) 738-8382

BOP STACK



CHOKE MANIFOLD




SELF-CERTIFICATION STATEMENT

Self-certification statement. Under the Federal regulation in effect as of June 15, 1988 designation of operator forms are no longer required when the operator is not the 100% record title holder. An operator is now required to submit a self-certification statement to the appropriate Bureau office stating that said operator has the right to operate upon the leasehold premises. Said notification may be in the following format:

"Please be advised that CNG Producing Company is considered to be the operator of Well No. 8-11F SE 1/4 of NE 1/4 Section 11, Township 10, Range 20E; Lease U-01790 Uintah County, Utah; and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by American Casualty Company of Reading, PA, Bond #524 7050.

CONFIDENTIAL



R. S. Gloger
Drilling Manager

DRILLING PLAN
APPROVAL OF OPERATIONS

Attachment for Permit to Drill

Name of Operator: CNG PRODUCING COMPANY

Address: CNG TOWER - 1450 POYDRAS STREET
NEW ORLEANS, LA 70112-6000

WELL LOCATION: Well No. 8-11F

Uintah, Utah

1. **GEOLOGIC SURFACE FORMATION**

Uintah

2. **ESTIMATE IMPORTANT GEOLOGIC MARKERS**

<u>Formation</u>	<u>Depth</u>
Wasatch Tongue	4280'
Green River Tongue	4610'
Wasatch	4750'
Chapita Wells	5460'
Uteland Buttes	6450'

CONFIDENTIAL

3. **ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS**

<u>Formation</u>	<u>Depth</u>	<u>Remarks</u>
Wasatch Tongue	4280'	Oil Zone
Chapita Wells	5460'	Gas Zone
Uteland Buttes	6450'	Gas Zone

4. **PROPOSED CASING PROGRAM**

8-5/8", 24#/ft, H-40, 0'-350' - Cemented to Surface
5½", 17#/ft, N-80 & K-55, 0'- 7300' - Cemented to Surface

5. **OPERATOR'S MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL**

BOP stack has a 3000 psi working pressure. BOP will be pressure tested to 2,700 psi before drilling casing cement plug. Pipe rams will be operated daily and blind rams as possible.

6. The well is to be drilled with a KCL mud system maintaining a weight of approximately 9#/gal.

7. AUXILIARY EQUIPMENT TO BE USED

1. Kelly Cock.
2. Full opening valve on floor with DP connection for use when Kelly is not in string.

8. TESTING, LOGGING, AND CORING PROGRAMS TO BE FOLLOWED

A mud logger will be used from 3,500' to TD. Possible DST in Wasatch Tongue. The logging program will include Dual Lateral/GR log TD to Surface, Density/Neutron - TD - 3,500' possible dipmeter and rotary cores over selected intervals.

9. ANTICIPATED ABNORMAL PRESSURES OR TEMPERATURES EXPECTED

No normal pressures are anticipated nor is the area known for abnormal temperatures. The formations to be penetrated do not contain H₂S gas. The anticipated bottom hole pressure is 2,610 PSI.

CONFIDENTIAL

10. WATER SUPPLY

- A. Water to be used for drilling will be hauled from Dalbo Trucking's well in Oray, Application #53617 User's Claim - Code #43 Serial #5496.
- B. No pipelines are anticipated. Hauling will be on the road(s) shown in Attachment No. 3.
- C. No water well is anticipated to be drilled at this time.

11. CEMENT SYSTEMS**SURFACE**

Flake +/-224 sks 25:75 Poz G cement, 2% S-I CaCl₂, .25#/sk D-29

PRODUCTION

Lead Slurry - 195 sk DS Hi-Lift, 3% D-44 Salt, 10#/sk D-42 Kolite, .25#/sk D-29 Celloflake.

Tail Slurry - 335 sk RFC 10-0 (thixotropic).

12. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS

Starting Date: June, 1994
Duration: 20 Days

SURFACE CASING CEMENT PROGRAM

Set 8 5/8" casing in 12 1/4" open hole cement to surface. Volume calculated using 75% excess.

SPACER:

Pump 20 BBLS lightly gelled water followed by 5 BBLS fresh H₂O ahead of cement to water wet the well bore after air drilling. Displace with fresh water.

CEMENT SYSTEM

± - 224 SK 25:75 Poz G "Tail-In" Cement, 2% S-1 CaCl₂, .25#/sk D-29 Celloflake.

Weight	15.40 lb/gal
Yield	1.11 ft ³ /sk
Water	4.71 gal/sk

CONFIDENTIAL

Thickening Time at 118°

1:42min.

Compressive Strength at 80°

8 hrs. 750 psi
16 hrs. 1800 psi
24 hrs. 2400 psi

CASING HARDWARE:

- 1 Cement Guide Shoe
- 1 Insert Float
- 3 Centralizers
- 1 Stop Ring
- 1 Thread Lock
- 1 Top Wood Plug

NOTE -

DS will at no charge (unless used), in addition to the casing cement, have 100 sk of cement, CaCl₂ for 2% by volume, and 80' to 100' of 1" tubing on location for top out job should cement not be returned to surface.

LONGSTRING CEMENT

Set 5 1/2" casing in a 7 7/8" open hole.
Lead cement slurry to fill from 750' above top pay zone to surface.
Tail cement slurry to fill from TD to 750' above the pay zone.
Both volumes are calculated using 15% excess.

SPACER:

(DAP Mud System) 20 BBL CW-100 (Sodium Silicate); 20 BBL Water
(KCL Mud System) 10 BBL water

Displace with 3% KCL water using .2% L-55 Clay Stabilizer in the first 50 bbl of displacement.

CEMENT SYSTEMS

CONFIDENTIAL

Lead Slurry

± - 195 sk DS Hi-Lift, 3% D-44 Salt, 10#/sk D-42 Kolite, .25#/sk D-29 Celloflake.

Weight	10.80 lb/gal
Yield	3.91 ft ³ /sk
Water	24.40 gal/sk

Thickening Time at 180°	4hrs +
Compressive Strengths in 24 hrs.	375 psi
Fluid Loss	240 cc/30 min.

Tail Slurry

± - 335 sk RFC 10-0 (thixotropic).

Weight	14.20 lb/gal
Yield	1.61 ft ³ /sk
Water	7.91 gal/sk

Thickening Time at 165 deg. BHCT	min.
Compressive Strength in 12 hrs.	845 psi
24 hrs.	1470 psi

Revised November 1990

Date NOS Received: _____

CONDITIONS OF APPROVAL
FOR THE SURFACE USE PROGRAM OF THE
APPLICATION FOR PERMIT TO DRILL

Company/Operator: CNG PRODUCING COMPANY

Well Name & Number: RBW 8-11F

Lease Number: U-01790

Location: SE/4 of NE/4 Sec. 11 T. 10S R. 20E

Surface Ownership: Bureau of Land Management

NOTIFICATION REQUIREMENTS

CONFIDENTIAL

Location Construction -
forty-eight (48) hours prior to construction of location and access roads.

Location Completion - prior to moving on the drilling rig.

Spud Notice - at least twenty-four (24) hours prior to spudding the well.

Casing String and Cementing - twenty-four (24) hours prior to running casing and cementing all casing strings.

BOP and Related Tests - twenty-four (24) hours prior to initiating pressure Equipment tests.

First Production Notice - within five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

B. THIRTEEN POINT SURFACE USE PROGRAM:

Multipoint Requirement to Accompany APD

1. Existing Roads - describe the following and provide a legible map, labeled and showing:
 - a. Proposed wellsite as staked and access route to location, including distances from point where access route exists establish roads. (Actual staking should include tow directional reference stakes.)
 - b. Route and distance from nearest town or locatable reference point, such as a highway or county road, to where well access route leaves main road.
 - c. Access road(s) to location color-coded or labeled.
 - d. Plans for improvement and/or maintenance of existing roads. (Appropriate rights-of-way for off lease roads should be attached.)
2. Planned Access Roads--describe the following and provide a map of suitable scale indicating all necessary access roads (permanent and temporary) to be constructed or reconstructed, showing:
 - a. Length - 200'
 - b. Width - 30 foot right-of-way with 18 foot running surface maximum.
 - c. Maximum grades - 8%
 - d. Turnouts - _____
 - e. Drainage design - Bar Pits
 - f. Location and size of culverts and/or bridges, and brief description of any major cuts and fills - None
 - g. Surfacing material (source) - Native
 - h. Necessary gates, cattleguards, or fence cuts and/or modification to existing facilities - None

(New or reconstructed roads are to be centerline-flagged at time of location staking.)

All travel will be confined to existing access road rights-of-way.

Access roads and surface disturbing activities will conform to standards outlined in the Bureau of Land Management and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development, (1989).

CONFIDENTIAL

The road shall be constructed/upgraded to meet the standards of the anticipated traffic flow and all-weather road requirements. Construction/upgrading shall include ditching, draining, graveling, crowning, and capping the roadbed as necessary to provide a well constructed safe road. Prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Traveling off the 30 foot right-of-way will not be allowed. Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossing nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided.

____ Right-of-Way Application needed.

CONFIDENTIAL

Not needed

____ The operator/lessee or his/her successor shall be responsible for all maintenance on cattleguards or gates associated with this oil and/or gas operation.

3. Location of Existing Wells - describe the following and provide a map or plat of all wells within a 1 mile radius of the proposed well location showing and identifying existing:

- a. Water wells - None
- b. Abandoned wells - None
- c. Temporarily abandoned wells - None
- d. Disposal wells - None
- e. Drilling wells - None
- f. Producing wells - RBU 8-2F, RBU 14-2F, RBU 10-2F, RBU 16-2F,
RBU 2-11F, RBU 3-11F, RBU 5-11F, RBU 7-11F,
RBU 9-11F, RBU 11-11F, RBU 9-10F, RBU 8-14F,
RBU 13-11F, 154, 169, 168, 162, 72N-3, 1-34,
35-1, 3
- g. Shut-in wells - None
- h. Injection wells - None

4. Location of Existing and/or Proposed Facilities

a. On well pad: Show the following existing area facilities and dimensions to be utilized if the well is successfully completed for production (detail painting plans and color if applicable):

- (1) Tank batteries
- (2) Production facilities
- (3) Oil gathering lines
- (4) Gas gathering lines
- (5) Injection lines
- (6) Disposal lines
- (7) Surface pits (separate application per NTL-2B requirements)

(Indicate if any of the above lines are buried.)

b. Off well pad: Same as above. Off lease flowlines may require rights-of-way or special use permits, check with the District Office Realty Specialist. (Include a diagram of the proposed attendant lines, i.e., flowlines, powerlines, etc., if off well pad location.)

- (1) Proposed location and attendant lines shall be flagged off of well pad prior to archaeological clearance.
- (2) Dimensions of facilities
- (3) Construction methods and materials
- (4) Protective measures and devices to protect livestock and wildlife

CONFIDENTIAL

Note: Operator has option of submitting information under 4A and B, after well is completed for production, by applying for approval of subsequent operations.

If storage facilities/tank batteries are constructed on this lease, the facility/battery or the well pad shall be surrounded by a containment dike of sufficient capacity to contain, at a minimum, the entire content of the largest tank within the facility/battery, unless more stringent protective requirements are deemed necessary by the authorized officer.

Tank batteries will be placed on the West side

All permanent (on site for six months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match on of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within 6 months of installation. Facilities required to comply with O.S.H.A. (Occupational Safety and Health Act) will be excluded.

The required paint color is Desert Tan.

If at any time the facilities located on public land and authorized by the terms of the lease are no longer included in the lease (due to a contraction in the unit or other lease or unit boundary change), BLM will process a change in authorization to the appropriate statute. The authorization will be subject to appropriate rental or other financial obligation as determined by the authorized officer.

CONFIDENTIAL

5. Location and Type of Water Supply

- a. Show location and type of water supply, either by 1/4, 1/4 section on a map or by written description Dalbo
- b. State method of transporting water, and show any roads or pipelines needed.
- c. If water well is to be drilled on lease, so state. _____

*The operator will be responsible for acquiring the necessary permit to obtain water to be used for drilling activities.

6. Source of Construction Materials

- a. Show information either on map or by written description - _____.
- b. Identify if from Federal or Indian (tribal or allotted) land.
- c. Describe where materials such as sand, gravel, stone, and soil material are to be obtained and used.

*If fill materials are needed to construct roads or well sites, proper permits must be obtained from the Surface Management Agency, unless materials are obtained from a private source.

*A mineral materials application (is/is not) required.

7. Methods of Handling Waste Disposal

- a. Describe methods and location of proposed safe containment and disposal of each type of waste material, including:
 - (1) Cuttings - bury in pit
 - (2) Sewage - haul to sewer lagoon
 - (3) Garbage (trash) and other waste material - haul to disposal
 - (4) Salts - not used
 - (5) Chemicals - non-toxic only; evaporate in pits
- b. Provide a plan for eventual disposal of drilling fluids and any produced oil or water recovered during testing operations. _____

*Burning will not be allowed. All trash must be contained in a trash cage and hauled away to an approved disposal site at the completion of the drilling activities.

On BLM administered lands:

The reserve pit shall be constructed so as not to leak, break, or allow discharge.

The reserve pit (shall/shall not) be lined if necessary to conserve water.

"If a plastic nylon reinforced liner is used, it will be a minimum of 10 mil thickness with sufficient bedding (either straw or dirt) to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash, scrap pipe, etc., that could puncture the liner will be disposed of in the pit. More stringent protective requirements may be deemed necessary by the A.O."

After first production, produced waste water will be confined to a lined pit or storage tank for a period not to exceed ninety (90) days. During the 90 day period, in accordance with NTL-2B, an application for approval of a permanent disposal method and location, along with required water analysis, shall be submitted for the AO's approval. Failure to file an application within the time allowed will be considered an incident of noncompliance.

On BIA administered lands:

CONFIDENTIAL

All reserve pits will be lined with either native clay, commercial bentonite or plastic sufficient to prevent seepage. (If a plastic nylon reinforced liner is used, it shall be torn and perforated after the pit dries and before backfilling of the reserve pit.)

— To protect the environment.
If the reserve pit is lined the operator will provide the BLM a chemical analysis of the fluids in that pit no later than 90 days after the well completion to determine the method for final reclamation of the reserve pit. If the elemental concentrations shown by the chemical analysis exceeds the requirements described by Part II, Standards of Quality for Waters of the State, Wastewater Disposal Regulations, State of Utah Division of Health, the contents and liner will be removed and disposed of at an authorized disposal site.

X To protect the environment (without a chemical analysis).

Reserve pits will be constructed so as not to leak, break, or allow discharge of liquids.

— Storage tanks will be used if drill sites are located on tribal irrigable land, flood plains, or on lands under crop production.

After first production, produced waste water will be confined to a lined pit or storage tank for a period not to exceed ninety (90) days. During the 90 day period, in accordance with NTL-2B, an application for approval of a permanent disposal method and location, along with required water analysis, shall be submitted for the AO's approval. Failure to file an application within the time allowed will be considered an incident of noncompliance.

8. Ancillary Facilities

Camp facilities or airstrips will not be allowed unless otherwise approved.

9. Well Site Layout--provide a plat (not less than 1" = 50') showing:

- a. Cross-sections of proposed drill pad with approximate cuts and fills and the relation to topography.
- b. Location of mud tanks, reserve, and flare pits, pipe racks, living facilities, and soil material stockpiles, etc. (Approval as used in this section means field approval of location.)
- c. Rig orientation, parking ares, and access roads, etc.

CONFIDENTIAL

The reserve pit will be located on the : Northeast corner

The flare pit will be located downwind of the prevailing wind direction on the East side a minimum of 100 feet from the well head and 30 feet from the reserve pit fence.

The stockpiled topsoil (first four inches) will be stored on the: South

Access to the well pad will be from the: Southwest

— Diversion ditch(es) shall be constructed on the _____ side of the location (above / below) the cut slope, draining to the _____.

— Soil compacted earthen berm(s) shall be placed on the _____ side(s) of the location around the _____.

— The drainage(s) shall be diverted around the _____ side(s) of the well pad location.

— The reserve pit and/or pad location shall be constructed long and narrow for topographic reasons _____.

X The northwest corner of the well pad will be rounded off to avoid the wash.

Fencing Requirements

All pits will be fenced according to the following minimum standards:

- a. 39-inch net wire shall be used with at least one stand of barbed wire on top of the net wire (barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence).

- b. The net wire shall be no more than 2-inches above the ground. The barbed wire shall be 3-inches above the net wire. Total height of the fence shall be at least 42-inches.
- c. Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times when pit is shrunk for production pit.
- d. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than 16 feet.
- e. All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three sides during drilling operations and on the fourth side when the rig moves off the location. Pits will be fenced and maintained until clean-up.

Each existing fence to be crossed by the access road shall be braced and tied off before cutting so as to prevent slacking of the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BLM or SMA specifications. A cattleguard with an adjacent 16 foot gate shall be installed in any fence where a road is to be regularly travelled. If the well is a producer, the cattleguard (shall/shall not) be permanently mounted on concrete bases. Prior to a new road, crossing any fence located on federal land, or any fence between federal land and private land, the operator will contact the BLM, who will in turn contact the grazing permittee or owner of said fence and offer him/her the opportunity to be present when the fence is cut in order to satisfy himself/herself that the fence is adequately braced and tied off.

10. Plans for Restoration of Surface

CONFIDENTIAL

a. Producing Location

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, materials, trash, and junk not required for production.

Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with 43 CFR 3162.7-1.

If a plastic nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 6 months from the date of well completion. Before any dirt work takes place, the reserve pit must be completely dry and all cans, barrels, pipe, etc., will be removed.

Contact appropriate surface management agency for required seed mixture.

b. Dry Hole/Abandoned Location

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and BLM will attach the appropriate surface rehabilitation conditions of approval.

On BIA administered lands:

Abandoned well sites, roads, or other disturbed areas will be restored to near their original condition. This procedure will include: (a) re-establishing irrigation systems where applicable, (b) re-establishing soil conditions in irrigated fields in such a way as to ensure cultivation and harvesting of crops and, (c) ensuring revegetation of the disturbed areas to the specifications of the Ute Indian Tribe or the BIA at the time of abandonment.

11. Surface Ownership:

Access Road: Bureau of Land Management

Location: Bureau of Land Management

"If the access road and/or location involves private or state agency owned surface, a copy of the surface owners agreement is required prior to approval of the APD."

12. Other Additional Information

CONFIDENTIAL

- a. The Operator is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator is to immediately stop work that might further disturb such materials, and contact the authorized officer (AO). Within five working days the AO will inform the operator as to :

-whether the materials appear eligible for the National Register of Historic Places;

-the mitigation measures the operator will likely have to undertake before the site can be used (assuming in situ preservation is not necessary); and

-a time frame for the AO to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the AO are correct and that mitigation is appropriate.

If the operator wishes, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the AO will assume responsibility for whatever recordation and stabilization of the exposed materials may be required. Otherwise, the operator will be responsible to mitigation costs. The AO will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the AO that required mitigation has been completed, the operator will then be allowed to resume construction.

- b. The operator will control noxious weeds along right-of-way for roads, pipelines, well sites, or other applicable facilities. A list of noxious weeds may be obtained from the BLM, or the appropriate County Extension Office. On BLM administered land it is required that a Pesticide Use Proposal shall be submitted, and given approval, prior to the application of herbicides or other pesticides or possible hazardous chemicals.
- c. Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on Federal Lands after the conclusion of drilling operations or at any other time without BLM authorization. However, if BLM authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities. (The BLM does not seek to compete with private industry. There are commercial facilities available for stacking and storing drilling rigs.)
- d. No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold panning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

On BIA administered land:

CONFIDENTIAL

Operator's employees, including subcontractors, will not gather firewood along roads constructed by operators. If wood cutting is required, a permit will be obtained from the Forestry Department of the BIA pursuant to 25 CFR 169.13 "Assessed Damages Incident to Right-of-Way Authorization". All operators, subcontractors, vendors and their employees or agents may not disturb salable timber (including firewood) without a duly granted wood permit from the BIA Forester.

If the surface rights are owned by the Ute Indian Tribe and mineral rights are owned by another entity, an approved rights-of-way will be obtained from the BIA before the operator begins any construction activities. If the surface is owned by another entity and the mineral rights are owned by the Ute Indian Tribe, rights-of-way will be obtained from the other entity.

All roads constructed by operators on the Uintah and Ouray Indian Reservation will have appropriate signs. Signs will be neat and of sound construction. They will state: (a) that the land is owned by the Ute Indian Tribe, (b) the name of the operator, (c) that firearms are prohibited to all non-Ute Tribal members, (d) that permits must be obtained from the BIA before cutting firewood or other timber products and (e) only authorized personnel permitted.

All well site locations on the Uinta and Ouray Indian Reservation will have an appropriate sign indicating the name of the operator, the lease serial number, the well name and number, the survey description of the well (either footages or the quarter-quarter section, the section, township, and range).

Additional Surface Stipulations

- ___ No construction or drilling activities shall be conducted between _____ and _____ because of _____

- ___ No surface occupancy will be allowed within 1,000 feet of any sage grouse strutting ground.
- ___ No construction or exploration activities are permitted within 1.5 mile radius of sage grouse strutting grounds from April 1 to June 30.
- ___ There shall be no surface disturbance within 600 feet of live water (includes stock tanks, springs, and guzzlers).
- ___ No cottonwood trees will be removed or damaged.
- X A silt catchment dam and basin will be constructed according to BLM specifications approximately 100 ft. north of the location, where flagged.
- _____

CONFIDENTIAL

13. Lessee's or Operators Representative and Certification

Representative

Name: _____

Address: _____

Phone No: _____

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved plan of operations, and any applicable Notice to Lessees. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

A complete copy of the approved APD and ROW grant, if applicable, shall be on location during construction of the location and drilling activities.

The operator or his/her contractor shall contact the BLM Office at (801) 789-1362 forty-eight (48) hours prior to construction activities.

The BLM Office shall be notified upon site completion prior to moving on the drilling rig.


Certification:

CONFIDENTIAL

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and, that the work associated with the operations proposed here will be performed by CNG Producing Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

April 21, 1994

Date

 David L. Linger

Senior Drilling Engineer

Name and Title

Onsite Date: April 20, 1994

Participants on Joint Inspection

Greg Darlington

Brent Stubbs

Val Fabrum

Randy Jackson

Darwin Kulland

Environmental Tech

Dirt Contractor

Dirt Contractor

Dirt Contractor

District Manager Production

CNG PRODUCING COMPANY ENGINEERS CALCULATION SHEET

CNG 116 (12/85)

FOR

LOCATION River Bend Unit

PAGE

SUBJECT Air service Equipment

DATE

Placement


BY Linger

Requirements:

① Blosie line Length - min 100' From Wellhead

② AIR SERVICE PACKAGE PLACEMENT

③ AS FAR FROM CATWALK AS POSSIBLE & ALLOW CLEAR PASSAGE FOR TRUCKS. ALLOW FOR MAX ANGLE FROM Blosie LINE




CONFIDENTIAL

CNGPRODUCING
COMPANY

LEGEND

□ = Oil Line
 G = Gas Line
 W = Water Line
 R = Relief Line (Pressure)
 C = Condensate Line
 V = Vent Line
 D = Drain Line
 M = Gas Meter
 P = Pump
 BP = Back Pressure Valve
 SWS = Sealed When Shipping
 SUS = Sealed Unless Shipping
 T = Heat Traced Line
 H = Heater
 BL = Buried Line
 ⋈ = Valve
 ⋈ = Check Valve
 SC = Sealed Closed Valve
 NC = Normally Closed
 BD = Blowdown Line



WELLHEAD (typ)

BL, G, C, W
(± 100')

BD, BL

PIT
30' x 30'
(typ)

W, BL

SEP

G, BL

GLYCOL
REBOILER
&
CONTACT
TOWER

GAS SALES LINE

±100'

BL, C

CONFIDENTIAL

Relief

300 bbl Tank
(condensate)

SC

SUS

The site security plan is on file in CNGP's district office located at 1400 N. State St., Roosevelt, Utah. It can be inspected during office hours, from 6:30 AM thru 3:30 PM, Monday thru Friday..

CNG PRODUCING COMPANY

Well: RBU 8-11F

RIVER BEND FIELD, UINTA COUNTY


not to scale

SDR\RBU\FLOW1SEP

TYPICAL FLOW DIAGRAM

date: 4/22/94

Located in the SE 1/4 of the NE 1/4 of
Section 11; T10S, R20E; S.L.B. & M.



APPROXIMATE QUANTITIES

CUT: 7300 yd³ (includes pit)
FILL: 4300 yd³

7 Apr '94 77-128-287



JERRY D. ALLRED & ASSOCIATES
Surveying & Engineering Consultants

121 North Center Street
P.O. Box 993
Duchesne, Utah 84021
(801) 726-0502

LEGEND

- INDIAN RESERVATION BOUNDARY
- PARTICIPATING AREAS A & B

CNG PRODUCING COMPANY RIVER BEND UNIT UINTAH COUNTY, UTAH 1991-92 DRILLING PROGRAM PARTICIPATING AREAS LAND PLAT

ZG2:[300,26]RBU8xIJV.DGN

Revised 9-7-93

RBU8-11F

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 04/25/94

API NO. ASSIGNED: 43-047-32512

WELL NAME: RBU 8-11F
OPERATOR: CNG PRODUCING COMPANY (N0605)

PROPOSED LOCATION:

SENE 11 - T10S - R20E
SURFACE: 1800-FNL-0500-FEL
BOTTOM: 1800-FNL-0500-FEL
UINTAH COUNTY
NATURAL BUTTES FIELD (630)

LEASE TYPE: FED
LEASE NUMBER: U-01790

PROPOSED PRODUCING FORMATION: WSTC

INSPECT LOCATION BY: / /

TECH REVIEW	Initials	Date
Engineering		
Geology		
Surface		

RECEIVED AND/OR REVIEWED:

Y Plat
Y Bond: Federal ☒ State ☐ Fee ☐
(Number 524 7050)
N Potash (Y/N)
Y Oil shale (Y/N)
Y Water permit
(Number 0ALBO)
N RDCC Review (Y/N)
(Date: _____)

LOCATION AND SITING:

☒ R649-2-3. Unit: UT4630541X
☐ R649-3-2. General.
☐ R649-3-3. Exception.
☐ Drilling Unit.
Board Cause no: _____
Date: _____

COMMENTS: _____

CONFIDENTIAL
PERIOD

EXPIRED
ON 7-2-96

STIPULATIONS: _____



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor

Ted Stewart
Executive Director

James W. Carter
Division Director

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340
801-359-3940 (Fax)
801-538-5319 (TDD)

June 3, 1994

CNG Producing Company
CNG Tower, 1450 Poydras Street
New Orleans, Louisiana 70112-6000

Re: RBU 8-11F Well, 1800' FNL, 500' FEL, SE NE, Sec. 11, T. 10 S., R. 20 E., Uintah County, Utah

Gentlemen:

Pursuant to Utah Code Ann. § 40-6-18, (1953, as amended), Utah Admin. R. 649-2-3, Application of Rules to Unit Agreements and R. 649-3-4, Permitting of Wells to be Drilled, Deepened or Plugged-Back, approval to drill the referenced well is hereby granted.

In addition, the following specific actions are necessary to fully comply with this approval:


1. Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules.
2. Notification to the Division within 24 hours after drilling operations commence.
3. Submittal of Entity Action Form, Form 6, within five working days following commencement of drilling operations and whenever a change in operations or interests necessitates an entity status change.
4. Submittal of the Report of Water Encountered During Drilling, Form 7.
5. Prompt notification prior to commencing operations, if necessary, to plug and abandon the well. Notify Frank R. Matthews, Petroleum Engineer, (Office) (801)538-5340, (Home) (801)476-8613, or K. Michael Hebertson, Reclamation Specialist, (Home) (801)269-9212.

Page 2
CNG Producing Company
RBU 8-11F Well
June 3, 1994

6. Compliance with the requirements of Utah Admin. R. 649-3-20, Gas Flaring or Venting, if the well is completed for production.

This approval shall expire one year after date of issuance unless substantial and continuous operation is underway or a request for an extension is made prior to the approval expiration date. The API number assigned to this well is 43-047-32512.

Sincerely,



R.J. Eirth
Associate Director

ldc

Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal District Office
WOH

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

(Other instruction
on reverse side)

Subsidiary Bureau No. 1304-0100
Expires August 31, 1985

DOGMA

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

5. LEASE DESIGNATION AND SERIAL NO
U-01790

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME
River Bend Unit

8. FARM OR LEASE NAME
RBU

9. WELL NO.
8-11F

10. FIELD AND POOL, OR WILDCAT
Island

11. SECS., T., R., M., OR BLK.
AND SURVEY OR AREA

SENE 11-T10S-R20E

12. COUNTY OR PARISH 13. STATE
Uintah Utah

a. TYPE OF WORK

DRILL [X]

DEEPEN []

PLUG BACK []

b. TYPE OF WELL

OIL WELL []

GAS WELL [X]

OTHER

SINGLE ZONE [] MULTIPLE ZONE []

2. NAME OF OPERATOR

CNG PRODUCING COMPANY

3. ADDRESS OF OPERATOR

CNG Tower, 1450 Poydras St., New Orleans, LA 70112-6000

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)*

At surface 500' FEL & 1,800' FNL of Sec. 11-T10S-R20E

At proposed prod. zone

Same

13-047.225-12

CONFIDENTIAL

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE
10 Miles SW of Ouray

15. DISTANCE FROM PROPOSED*
LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.

(Also to nearest drlg. unit line if any)

500'

16. NO. OF ACRES IN LEASE

160

17. NO. OF ACRES ASSIGNED
TO THIS WELL

80

18. DISTANCE FROM PROPOSED LOCATION*
TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE,

1,508'

19. PROPOSED DEPTH

7,300'

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)
5,043' GR

22. APPROX. DATE WORK WILL START
June, 1994

23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12 1/4"	8 5/8"	24#	+/- 350	Cement to Surface
7 7/8"	5 1/2"	17#	+/- 7,300	Cement Calc to Surface

1. Drill a 12 1/4" hole with an air rig to +/- 350', run 8 5/8", H-40 casing and cement to surface.

2. NU and pressure test BOP stack prior to drilling out below surface pipe.

3. Operate pipe rams daily and blind rams as possible.

4. Drill a 7 7/8" hole to 7,300' with a salt water mud system. Coring is possible. DST's will be run as needed to evaluate unexpected shows.

5. Run logs, set 5 1/2", 17#, N 80 & K-55 casing as dictated by drilling shows, tests, and logs. Casing program may be modified to provide added burst strength if needed for frac program.

6. Primary zones of interest are the Wasatch, Chapita Wells & Uteland Buttes.

7. All zones indicating potential for economically recoverable reserves will be tested in a normal, prudent manner.


8. In the event of lost circulation, air or air assisted mud will be utilized.

FORMATION TOPS	DEPTHS
Wasatch	4,750'
Chapita Wells	5,460'
Uteland Buttes	6,450'

CONFIDENTIAL

RECEIVED

APR 25 1994



CNG Producing respectfully request that all information concerning this well be held confidential.

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true verticle depth. Give blowout preventer program, if any.

24.

SIGNED

David L. Linger

TITLE Senior Drilling Engineer

DATE 4/21/94

PERMIT NO.

NOTICE OF APPROVAL

APPROVAL DATE

CONDITIONS OF APPROVAL ATTACHED
TO OPERATOR'S COPY

APPROVED BY

TITLE

ASSISTANT DISTRICT
MANAGER MINERALS

DATE JUN 06 1994

CONDITIONS OF APPROVAL, IF ANY:

*See Instructions On Reverse Side

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

44-080-4M-093

WELL LOCATION INFORMATION

Company/Operator: CNG Producing Company

API Number 43-047-32512

Well Name & Number: RBU 8-11F

Lease Number: U-01790

Location: SENE Sec. 11 T.10 S. R.20 E.

Surface Ownership: BLM

Date NOS Received April 12, 1994

Date APD Received April 25, 1994

NOTIFICATION REQUIREMENTS

- Location Construction - at least forty-eight (48) hours prior to construction of location and access roads.
- Location Completion - prior to moving on the drilling rig.
- Spud Notice - at least twenty-four (24) hours prior to spudding the well.
- Casing String and Cementing - at least twenty-four (24) hours prior to running casing and cementing all casing strings.
- BOP and Related Equipment Tests - at least twenty-four (24) hours prior to initiating pressure tests.
- First Production Notice - within five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Company CNG Producing Company Well No. RBU 8-11F

Location SENE, Section 11, T10S, R20E Lease No. U - 01790

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered

Report ALL water shows and water-bearing sands to Tim Ingwell of this office. Copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment

The BOP and related equipment shall meet the minimum requirements of onshore Oil and Gas Order No. 2 for a 3M system for equipment and testing requirements, procedures, etc., and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

If an air compressor is on location and is being utilized to provide air for the drilling medium while drilling, the special drilling requirements in Onshore Oil and Gas Order No. 2, regarding air or gas drilling shall be adhered to. If a mist system is being utilized then the requirement for a deduster shall be waived.

3. Casing Program and Auxiliary Equipment

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

As a minimum, the usable water and oil shale resources shall be isolated and/or protected by having a cement top for the production casing at least 200 ft. above the top of the Mahogany oil shale, identified at $\pm 2,284$ ft. If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

All Drill Stem tests (DST) shall be accomplished during daylight hours, unless specific approval to start during other hours is obtained from the AO. However, DSTs may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e., lighting which is adequate for visibility and vapor-proof for safe operations). Packers can be released, but tripping should not begin before daylight unless prior approval is obtained from the AO.

A cement bond log (CBL) will be run from the production casing shoe to $\pm 2,084$ ft. and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. Two copies of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communication, not later than five (5) days following the date on which the well is placed on production.

Gas produced from this well may not be vented or flared beyond an initial authorized test period of 30 days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the Authorized Officer. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

A schematic facilities diagram as required by 43 CFR 3162.7-2, 3162.7-3, and 3162.7-4 shall be submitted to the appropriate District Office within thirty (30) days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-4.

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling on-lease or off-lease will have prior written approval from the AO.

Gas meter runs for each well will be located within 500 feet of the wellhead. The gas flowline will be buried or anchored down from the wellhead to the meter and within 500 feet downstream of the meter run or any production facilities. Meter runs will be housed and/or fenced.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted monthly for the first three months on new meter installations and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approvals are necessary, please contact one of the following individuals:

Ed Forsman Petroleum Engineer	(801) 789-7077
Wayne Bankert Petroleum Engineer	(801) 789-4170
BLM FAX Machine	(801) 781-4410

EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous.

Unused fracturing fluids or acids

Gas plant cooling tower cleaning wastes

Painting wastes

Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spent solvents, spilled chemicals, and waste acids

Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste

Refinery wastes

Liquid and solid wastes generated by crude oil and tank bottom reclaimers

Used equipment lubrication oils

Waste compressor oil, filters, and blowdown

Used hydraulic fluids

Waste solvents

Waste in transportation pipeline-related pits

Caustic or acid cleaners

Boiler cleaning wastes

Boiler refractory bricks

Incinerator ash

Laboratory wastes

Sanitary wastes

Pesticide wastes

Radioactive tracer wastes

Drums, insulation and miscellaneous solids.

CONDITIONS OF APPROVAL
SURFACE USE PLAN OF OPERATIONS

No construction or drilling activities shall be conducted between May 15 and June 20 because of crucial pronghorn habitat. Modifications to the surface use plan to protect the pronghorn are required during their kidding period.

No silt catchment dam and basin will be constructed. A review of the project led BLM to recommend that the silt catchment requested at the onsite not be built.

The pit shall be constructed and lined with a 10 mil liner to conserve water, as described in the APD. If blasting is required to dig the reserve pit, then a liner of at least 12 mil thickness will be used to insure that the pit will not leak.

The access road would enter the pad between stakes 7 and 8 and about 5 feet south of stake 8 as per discussion at the onsite. The APD shows it entering across corner 8.

CONFIDENTIAL

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

NAME OF COMPANY: CNG PRODUCING

WELL NAME: RBU 8-11F

API NO. 43-047-32512

Section 11 Township 10S Range 20E County UINTAH

Drilling Contractor CIRCLE L

Rig # 18

SPUDDED: Date 7/28/94

Time

How DRY HOLE

Drilling will commence

Reported by DWH-DOGM

Telephone #

Date 8/1/94 SIGNED JLT

ENTITY ACTION FORM - FORM 6

ADDRESS CNG Tower
1450 Poydras Street
New Orleans, LA 70112-6000

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
B	99999	07050	43-047-32512	RBW 8-11F	SE NE	11	10S	20E	Uintah	08/02/94	
WELL 1 COMMENTS: This well is located within River Bend Unit on BLM land. Entity added 8-31-94. Lee											
WELL 2 COMMENTS:											
WELL 3 COMMENTS:											
WELL 4 COMMENTS:											
WELL 5 COMMENTS											

ACTION CODES (See instruction on back of form)

- A - establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

(3/89)

Susan H. Sachitara
SignatureRegulatory Specialist
TitleAugust 25, 1994
DatePhone No. (504) 593-7260

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT**CONFIDENTIAL**FORM APPROVED
BUDGET BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well
☐ Oil Well ☒ Gas Well ☐ Other2. Name of Operator
CNG PRODUCING COMPANY3. Address and Telephone No.
CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-60004. Location of Well (Footage, Sec., T., R., M., or Survey Description)
Surface 500' FEL & 1,800' FNL of Sec. 11-T10S-R20E5. Lease Designation and Serial No.
U-01790

6. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation
River Bend Unit8. Well Name and No.
8-11F9. API Well No.
43-047-3251210. Field and Pool, or Exploratory Area
Island11. County or Parish, State
Uintah, Utah

CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent☒ Subsequent Report☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment☐ Recompletion☐ Plugging Back☐ Casing Repair☐ Altering Casing☒ Other - Spud Notice☐ Change of Plans☐ New Construction☐ Non-Routine Fracturing☐ Water Shut-Off☐ Conversion to Injection☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

This is to notify you that the RBU 8-11F was spudded by Leon Ross Drilling on 8-2-94.

They drilled 379' of 12 1/4" hole and ran 9 jts of 8 5/8" 24# J-55 casing, float, 3 centralizers, and shoe set at 377.88'.

Cemented with 224 sks 25/75 Pozmix with 2% Calc2, and .25#/sk D-29 flake.
Cement to surface. Plug bumped OK. Good circulation.

14. I hereby certify that the forgoing is true and correct

Signed David L. Linger Title Senior Drlg Engineer Date August 25, 1994

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____
Conditions of approval, if any: _____

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

RECEIVED

AUG 29 1994

1. Well name and number: RBU 8-11FAPI number: 43-047-325122. Well location: QQ SE NE section 11 township 10S range 20E county UintahDIVISION OF
OIL, GAS & MINING3. Well operator: CNG Producing CompanyAddress: CNG Tower - 1450 Poydras Street phone: (504) 593-7000
New Orleans, LA 70112-60004. Drilling contractor: Circle L DrillingAddress: 826 South 1500 East phone: (801) 781-2069
Vernal, UT 84078


5. Water encountered (continue on reverse side if necessary)

Depth		Volume (flow rate or head)	Quality (fresh or salty)
from	to		
2,700'	2,900'	100 BPH	Fresh

6. Formation tops: Wasatch Tongue 4,280'

If an analysis has been made of the water encountered, please attach a copy of the report to this form.

I certify that this report is true and complete to the best of my knowledge.

Name David L. Linger
Title Senior Drilling EngineerSignature 
Date August 25, 1994

Comments:

This water flow was encountered while drilling with 292 GPM pump rate and 400 CFM air rate. The approximate fluid weight at the time this water flow was encountered is equal to a 5.0 PPG

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

DIV. OF OIL, GAS & MINING

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

5. Lease Designation and Serial No.
U-01790

6. If Indian, Allottee or Tribe Name

SUBMIT IN TRIPLICATE

1. Type of Well [] Oil Well [X] Gas Well [] Other	7. If Unit or CA, Agreement Designation River Bend Unit
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 8-11F
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No. 43-047-32512
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface 500' FEL & 1,800' FNL of Sec. 11-T10S-R20E	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

[] Notice of Intent

[] Abandonment

[] Change of Plans

[X] Subsequent Report

[] Recompletion

[] New Construction

[] Plugging Back

[] Non-Routine Fracturing

[] Casing Repair

[] Water Shut-Off

[] Final Abandonment Notice

[] Altering Casing

[] Conversion to Injection

[X] Other - Weekly Report

[] Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

August 22, 1994 - August 26, 1994

Rig up rig. Nipple up BOPs. Test BOPs, blind rams, manifold, choke, pipe rams, floor valve and kelly valve to 3000 PSI. Tested OK. Tested annular and 8 5/8" casing to 1500 PSI. Tested OK. Pick up bit and tag cement at 300'. Drill to 348'. Rig service. Drill baffle, cement and shoe at 391'. Survey at 370'. Drill to 890'. Survey at 890'. Drilling with aerated fluid. Survey at 1,390'. Drilling with aerated fluid. Survey at 1,913'. Drilling with aerated fluid. Survey at 2,429'. Drilling with aerated fluid. Water flow at 2,700-2,900'. Survey at 2,943'. Drilling with aerated fluid. Survey at 3,439'. Drilling with fluid. Lost mud weight and pressure. Trip out of hole with 11 stands. Twisted off 1.90' below box. Wait on fishing tools. Pick up 7 1/16 x 4 1/2 OS. Trip in hole. Work overshot over fish. Trip out of hole with fish and fishing tools. Bit OK. Trip in hole. Wash 45' to bottom. Drilling with fluid. Survey at 3,936'. Drilling with fluid. Mud wt. 8.6 ppg. TD at 4,290'.

14. I hereby certify that the forgoing is true and correct

Signed Susan H. Sachitana Title

Regulatory Specialist

Date

August 26, 1994

Susan H. Sachitana

(This space for Federal or State office use)

Approved by _____ Title _____

Date _____

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side


UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
BUDGET BUREAU NO. 1004-0135
DUE DATE: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		7. If Unit or CA, Agreement Designation River Bend Unit
2. Name of Operator CNG PRODUCING COMPANY		8. Well Name and No. 8-11F
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-2500		9. API Well No. 43-047-32512
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface 500' FEL & 1,800' FNL of Sec. 11-T10S-R20E		10. Field and Pool, or Exploratory Area Island
		11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☐ Notice of Intent

☐ Abandonment

☐ Change of Plans

☒ Subsequent Report

☐ Recompletion

☐ New Construction

☐ Final Abandonment Notice

☐ Plugging Back

☐ Non-Routine Fracturing

☐ Casing Repair

☐ Water Shut-Off

☐ Altering Casing

☐ Conversion to Injection

☒ Other - Weekly Report

☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

August 27, 1994 - September 2, 1994

Drilling with fluid. Survey at 4,492'. Drilling with fluid. Survey at 5,004'. Drilling with fluid. Rig service. Drill with fluid. Lost 150# pressure. Trip out of hole with bit. Found holes 15th, 32nd and 47th stand. Pick up bit. Trip in hole with bit. Wash and ream 100' to bottom. Drilling with fluid. Survey at 5,663'. Drilling with fluid. Repair air line. Drilling with fluid. Drilling with fluid to 6,212'. Survey at 6,138'. Drilling with fluid. Lost pressure. Trip out of hole. Found cracked box 20 stands. Circulate. Test pressure. Trip in hole. Drilling with fluid. Survey at 6,637'. Drilling with fluid. Close in system and mud up at 6,850'. Repair - pumps aired up. Drilling with fluid. Pumped LCM sweep at 6,900'. Drilling with fluid. Circulate for logs. Short trip 10 stands. Circulate for logs. Trip out of hole. SLM - 6,997'. Rig up Halliburton logging and trip in hole. Ran spectral density - TD - 2,000', neutron - TD - 2,000', and dual laterolog - TD - surface. Loggers TD at 7,002'. Trip in hole. Rig up and lay down drill pipe and drill collars. Run 5 1/2" casing and land at 6,518'. Rig up Dowell. Circulate. Cement with 380 sks HiLift, 12% D-20, 1% D-79, .1% D-112, 3% D-44, 10#/sk D-42, .25#/sk D-29, .2% D-46 followed by 760 sks 10-0 RFC. Displaced with 149 bbls 2% KCL, L-55. Good returns. Cement to surface. Bumped plug with 2500 PSI. Set slips. Nipple down BOPs. Clean mud tanks. Released rig on 9/1/94.

14. I hereby certify that the forgoing is true and correct

Signed Susan Sachitana Title Regulatory Specialist Date September 2, 1994
Susan H. Sachitana

(This space for Federal or State office use)


Approved by _____ Title _____ Date _____

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT



FORM APPROVED

BUDGET BUREAU NO. 1004-0135

EXPIRES: MARCH 31, 1993

5. Lease Designation and Serial No.

U-01790

6. If Indian, Allottee or Tribe Name

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT" for such proposals.

SUBMIT IN TRIPLICATE

- | | |
|--|--|
| 1. Type of Well
[] Oil Well [X] Gas Well [] Other | 7. If Unit or CA, Agreement Designation
River Bend Unit |
| 2. Name of Operator
CNG PRODUCING COMPANY | 8. Well Name and No.
8-11F |
| 3. Address and Telephone No.
CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000 | 9. API Well No.
43-047-32512 |
| 4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
Surface 500' FEL & 1,800' FNL of Sec. 11-T10S-R20E | 10. Field and Pool, or Exploratory Area
Island |
| | 11. County or Parish, State
Uintah, Utah |

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

[] Notice of Intent

[] Abandonment

[] Change of Plans

[X] Subsequent Report

[] Recompletion

[] New Construction

[] Final Abandonment Notice

[] Plugging Back

[] Non-Routine Fracturing

[] Casing Repair

[] Water Shut-Off

[] Altering Casing

[] Conversion to Injection

[X] Other - Weekly Report

[] Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

CONFIDENTIAL

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

October 20, 1994 - October 21, 1994

Rig up Western to casing. Establish injection rate on Zone #1 (6,134-52' & 6,304-10') with 26 bbls of 2% KCL water. Zone broke at 3180 PSI. Treated zone with 1075 bbls of fluid and 140,000 lbs of 20/40 frac sand. Had wet sand. Couldn't get last 10,000 lbs of sand pumped. Average injection rate was 25 BPM and average treating pressure was 2500 PSI. Open casing to pit on 18/64 choke after flowing for 2 hrs.

14. I hereby certify that the forgoing is true and correct

Signed Susan Sachitana Title Regulatory Specialist Date October 21, 1994
Susan H. Sachitana


(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

UNITED STATES
 DEPARTMENT OF THE INTERIOR
 BUREAU OF LAND MANAGEMENT

 FORM APPROVED
 BUDGET BUREAU NO. 1004-0138
 EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT..." for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well [] Oil Well [X] Gas Well [] Other	7. If Unit or CA, Agreement Designation River Bend Unit
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 8-11F
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No. 43-047-32512
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface 500' FEL & 1,800' FNL of Sec. 11-T10S-R20E	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

[] Notice of Intent

[] Abandonment

[] Change of Plans

[] Recompletion

[] New Construction

[X] Subsequent Report

[] Plugging Back

[] Non-Routine Fracturing

[] Casing Repair

[] Water Shut-Off

[] Final Abandonment Notice

[] Altering Casing

[] Conversion to Injection

[X] Other - Weekly Report

[] Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

CONFIDENTIAL

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

October 22, 1994 - October 28, 1994

Well flowing to pit with 1/4" stream of water only. Zero tubing pressure. No gas. Removed 18/64 choke. Installed 18/64 choke. Still no increase or change in pressure. No water. 1/4" steady stream of water. No gas. Still flowing 1/4" stream of water only. No gas. Removed choke. No increase or change in pressure. 1/4" stream of water. No gas. Flowing well to pit. Removed choke. 1/4" stream of water only. No gas. Installed choke. No change in pressure. 1/4" stream of water. No gas. Flowing tubing to pit on 18/64 choke with 1/4" stream of water. No gas. No flow on casing. Removed 18/64 choke. Had 1/8" flow. No pressure. Took water sample of fluid. Sent sample to Western yard. Left casing open on 2" line. No choke. Rig up Schlumberger. Run in hole with 5 1/2" bridge plug. Set bridge plug at 6,050'. Tag bridge plug. Pull out of hole. Pressure test bridge plug to 2800 PSI. Key stack on hot oil truck sheared. Wasn't able to pressure up to 3500 PSI. Run in hole with 4" casing gun with 2 SPF. Perforate Zone II (5,944-64'). Pull out of hole. Rig down wireline truck. Rig up Western to casing. Establish injection rate for Zone II (5,944-64') with 22 bbls 2% KCL water. Zone broke at 2850 PSI. Treated zone with 211,500 bbls of 20/40 frac sand and 1,454 bbls of fluid. Average treating pressure was 2000 PSI. Open casing to pit on 18/64 choke.

14. I hereby certify that the forgoing is true and correct

Signed Susan H. Sachitana Title

Regulatory Specialist

Date

October 28, 1994

Susan H. Sachitana

(This space for Federal or State office use)

Approved by _____

Title _____

Date _____

Conditions of approval, if any: _____

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

**CNG Producing
Company**

OCT 3 1 1994

A CNG COMPANY

CNG Tower
1450 Poydras Street
New Orleans, LA 70112-6000
(504) 593-7000

October 27, 1994

Mr. Paul M. Andrews
Area Manager, Books Cliff Resource Area
U.S. Dept. of the Interior
Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, UT 84078

RE: River Bend Unit
Application for Disposal Pits

Dear Mr. Andrews:

Enclosed please find an original and two copies of Sundry Form 3160-5 requesting approval for a second disposal pit at the following locations:

<u>Well Name</u>	<u>Location</u>	<u>Lease Number</u>
RBW 8-11F	SE NE 11-T10S-R20E	U-01790
RBW 9-14EO	NE SE 14-T10S-R19E	U-013792
RBW 5-24EO	SW NW 24-T10S-R19E	U-013794
RBW 1-25E	NE NE 25-T10S-R19E	U-73011

CNG is applying for these disposal pits under the criteria that these wells do not produce more than 5 barrels per day, therefore the following information is not applicable:

1. Water Analysis
2. There are no known aquifers in the area.

Should you have any question please feel free to contact me at (504) 593-7260.

Sincerely,

CNG PRODUCING COMPANY

Susan H. Sachitana

Susan H. Sachitana
Regulatory Specialist

Enclosure

cc: Utah Board of Oil Gas & Mining
Darwin Kulland
Yvonne Abadie

UNITED STATES
 DEPARTMENT OF THE INTERIOR
 BUREAU OF LAND MANAGEMENT

 RECEIVED
 OCT 31 1994

 FORM APPROVED
 BUDGET BUREAU NO. 1004-0135
 EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well [] Oil Well [X] Gas Well [] Other	7. If Unit or GA, Agreement Designation River Bend Unit
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 8-11F
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No. 43-047-32512
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface 500' FEL & 1,800' FNL of Sec. 11-T10S-R20E	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

[X] Notice of Intent

[] Abandonment

[] Change of Plans

[] Recompletion

[] New Construction

[] Subsequent Report

[] Plugging Back

[] Non-Routine Fracturing

[] Casing Repair

[] Water Shut-Off

[] Final Abandonment Notice

[] Altering Casing

[] Conversion to Injection

[] Other

[X] Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

Pursuant to Onshore Order #7 effective October 8, 1993, CNG Producing Company hereby makes application under Section 3.D.2.iv. The pit dimensions would be 15' x 15' with a minimum of 2' of free-board adjacent to the dehy dump. The pit shall be fenced or enclosed to prevent access by livestock, wildlife and unauthorized personnel.

The volume of water to be disposed of does not exceed an average of 5 barrels per day of a monthly basis.

The evaporation rate in the area is 4' per year and the percolation rate of the soil is approximately 1" per day.

14. I hereby certify that the forgoing is true and correct

 Signed Susan H. Sachitana Title Regulatory Specialist Date October 25, 1994
 Susan H. Sachitana

(This space for Federal or State office use)

 Approved by _____ Title _____ Date _____
 Conditions of approval, if any:

 Accepted by the
 Utah Division of
 Oil, Gas and Mining

FOR RECORD ONLY

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
BUDGET BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Designation River Bend Unit
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 8-11F
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No. 43-047-32512
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface 500' FEL & 1,800' FNL of Sec. 11-T10S-R20E	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☐ Notice of Intent☐ Abandonment☐ Change of Plans☒ Subsequent Report☐ Recompletion☐ New Construction☐ Final Abandonment Notice☐ Plugging Back☐ Non-Routine Fracturing☐ Casing Repair☐ Water Shut-Off☐ Altering Casing☐ Conversion to Injection☒ Other - Weekly Report☐ Dispose Water


(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

CONFIDENTIAL

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

October 29, 1994 - November 4, 1994

No flow. Pulled choke. Run thru 2" flowline. Well came around. Put on 18/64 choke. Returning straight gas. No fluids. No mist. Flow testing Zone II (5,944-64'). Flowing casing to pit on 18/64 choke with 25 PSI on casing. No fluids. Gas rate 51,000. Rig up Schlumberger. Run in hole with 5 1/2" bridge plug. Set bridge plug at 5,820'. Pull out of hole. Rig up hot oil truck to casing. Filled hole and pressure test bridge plug to 3500 PSI. with 60 bbls 2% KCL water. Run in hole with 4" casing gun. Perforate Zone #3 (5,726-44') with 2 SPF. Pull out of hole. Rig down wireline truck. Rig up Western to casing. Establish injection rate on Zone #3 (5,726-44') with 36 bbls of 2% KCL water. Zone broke at 2400 PSI. Treated zone with 1,151 bbls of fluid and 156,660 lbs of 20/40 frac sand. Average treating pressure was 2800 PSI. Opened casing to pit on 18/64 choke.



14. I hereby certify that the forgoing is true and correct

Signed Susan SachitanaTitle Regulatory Specialist

Date

November 4, 1994

Susan H. Sachitana

(This space for Federal or State office use)


Approved by

Title

Date

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
 DEPARTMENT OF THE INTERIOR
 BUREAU OF LAND MANAGEMENT

 FORM APPROVED
 BUDGET BUREAU NO. 1004-0135
 EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT TO DRILL" for such proposals.

 5 Lease Designation and Serial No.
 U-01790

6 If Indian, Allottee or Tribe Name

SUBMIT IN TRIPLICATE

- | | |
|--|--|
| 1. Type of Well
<input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other | 7. If Unit or GA, Agreement Designation
River Bend Unit |
| 2. Name of Operator
CNG PRODUCING COMPANY | 8. Well Name and No.
8-11F |
| 3. Address and Telephone No.
CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000 | 9. API Well No.
43-047-32512 |
| 4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
Surface 500' FEL & 1,800' FNL of Sec. 11-T10S-R20E | 10. Field and Pool, or Exploratory Area
Island |
| | 11. County or Parish, State
Uintah, Utah |

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☐ Notice of Intent☐ Abandonment☐ Change of Plans☒ Subsequent Report☐ Recompletion☐ New Construction☐ Final Abandonment Notice☐ Plugging Back☐ Non-Routine Fracturing☐ Casing Repair☐ Water Shut-Off☐ Altering Casing☐ Conversion to Injection☒ Other - Weekly Report☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

CONFIDENTIAL

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

November 5, 1994 - November 11, 1994

Flow testing Zone #3 (5,726-44'). After flowing casing to pit for 17 hrs, well had 25 PSI on casing. Well returning gas and 1/4" stream of water. Removed 18/64 choke. Left casing open to pit on 2" line. Blowing straight gas with 5 second surges of heavy mist every 15 minutes. Replaced 18/64 choke. Clean with intermittent mist. Returning 497 MCF gas. Flowing straight gas surges with heavy mist every 30 minutes. Flowing gas at 538 MCF. Rig up Western to casing. Injection rate with 57 bbls of 2% KCL water. Zone #4 (4,838-52') broke at 1750 PSI. Treated zone with 950 bbls of fluid and 127,320 lbs of 20/40 frac sand. Average treating pressure 2750 PSI. Open casing to pit on 18/64 choke.

14. I hereby certify that the forgoing is true and correct

 Signed Susan H. Sachitana Title Regulatory Specialist Date November 11, 1994
 Susan H. Sachitana

(This space for Federal or State office use)

 Approved by _____ Title _____ Date _____
 Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

RECEIVE

NOV 21 1994

Form Approved
BUDGET BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993
5. Lease Designation and Serial No.
U-01790

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT TO DRILL FOR OIL, GAS & MINING"

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Designation River Bend Unit
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 8-11F
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No. 43-047-32512
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface 500' FEL & 1,800' FNL of Sec. 11-T10S-R20E	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☐ Notice of Intent

☐ Abandonment

☐ Change of Plans

☐ Recompletion

☐ New Construction

☒ Subsequent Report

☐ Plugging Back

☐ Non-Routine Fracturing

☐ Casing Repair

☐ Water Shut-Off

☐ Final Abandonment Notice

☐ Altering Casing

☐ Conversion to Injection

☒ Other - Weekly Report

☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

CONFIDENTIAL

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

November 12, 1994 - November 18, 1994

Flowing 1/4" stream of water to pit. Removed choke, 1/2" stream of water to pit. No change in pressure, still 1/2" stream of water. Choke will be removed overnight. Still flowing 1/2" stream of water. No gas. Choke is still out. Estimated 20 bbls of water. Well still flowing 1/2" stream of water and no gas. Choke was out. Casing pressure was 400 PSI. Discharging both water & light skim of oil. Well is heading or unloads, every second, gas, water. Installed 18/64 choke with 400 PSI on casing blowing heavy wet gas with light yellow crude oil. Flow testing Zone #4 (4,838-52'). Flowing casing to pit on 18/64 choke. Gas rate 310 MCF with 150 PSI on casing. Returning gas and treating fluid. Left casing flowing on 18/64 choke. Flowing Zone #4 (4,838-52') to pit on 18/64 choke with 150 PSI on casing. Returning 310 MCF gas and mist of treating fluid. Rig up Schlumberger. Run in hole with 5 1/2" bridge plug. Set bridge plug at 4,310'. Tag bridge plug. Pressure test bridge plug to 3500 PSI. Tested OK. Run in hole with 4" casing gun loaded with 2 SPF. Perforate Zone A (4,236-48' & 4,252-58'). Rig up rig and equipment. Pick up 5 1/2" Baker R-3 Packer and seating nipple. Pick up and run in hole with 135 jts. End of tubing at 4,213'. No pressure on well. Run in hole with tubing to 4,264'. Rig up Western to tubing. Filled hole with 2% KCL water. Pressure up to 1000 PSI to break circulation. Return small amount of green oil. Spot 2 sks 20/40 frac sand on bridge plug at 4,310'. Pull up to 3,993'. Set packer. Pressure up casing to 500 PSI. Rig up Western to tubing. Pump 8 bbls 2% KCL water. Treated Zone A (4,236-48' & 4,252-58') then dropped 60 ball sealers. Had small amount of action. Didn't ball off. After acid reached perforation, pressure fell off from 4,200 PSI to 3000 PSI. Increase rate from 2.2 to 5.7 BPM. Total treating fluid 101.5 bbls. Flowed tubing to pit. Well had 100 PSI on tubing. Open tubing to pit on 2" line flowing 20 bbls of water per hr. No oil. Flowed well for 8 hrs. Flowed back 160 bbls. Caught water sample. Shut-in well.

14. I hereby certify that the foregoing is true and correct

Signed Susan Sachitana Title Regulatory Specialist Date November 18, 1994
Susan H. Sachitana

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
 DEPARTMENT OF THE INTERIOR
 BUREAU OF LAND MANAGEMENT

RECEIVED

NOV 28 1994

FORM APPROVED

BUDGET BUREAU NO. 1004-0135

EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen a well in a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals.

DIV OF OIL, GAS & MINING

5. Lease Designation and Serial No.

U-01790

6. If Indian, Allottee or Tribe Name

SUBMIT IN TRIPLICATE

1. Type of Well

[] Oil Well [X] Gas Well [] Other

2. Name of Operator

CNG PRODUCING COMPANY

3. Address and Telephone No.

CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

Surface 500' FEL & 1,800' FNL of Sec. 11-T10S-R20E

7. If Unit or GA, Agreement Designation
River Bend Unit

8. Well Name and No.

8-11F

9. API Well No.

43-047-32512

10. Field and Pool, or Exploratory Area
Island

11. County or Parish, State

Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

[] Notice of Intent

[] Abandonment

[] Change of Plans

[X] Subsequent Report

[] Recompletion

[] New Construction

[] Final Abandonment Notice

[] Plugging Back

[] Non-Routine Fracturing

[] Casing Repair

[] Water Shut-Off

[] Altering Casing

[] Conversion to Injection

[X] Other - Weekly Report

[] Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

CONFIDENTIAL

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

November 19, 1994 - November 23, 1994

Release packer. Pull out of hole with 8 jts. Set packer at 3,738'. Rig up Western to tubing. Establish injection rate with 8 bbls 2% KCL water at 3.2 BPM and 1000 PSI. Pump 5 bbls fresh water spacer. Pump 50 sks Type G cement with 2% CaCl and .5% TF-4. Pump 3 bbls into perforations. Started stages. Squeeze off perforations. Pressure up to 2000 PSI twice. Release packer. Circulate tubing clean with 40 bbls 2% KCL water. Pull out of hole with 8 jts. Set packer at 3,490'. Pressure up tubing to 1000 PSI. Let cement set overnight to cure. Left 1000 PSI on tubing after squeeze job. Tubing has 900 PSI. Bled off pressure. Release packer. Pull out of hole with 112 jts. Lay down packer. Run in hole with 4 3/4" bit sub and casing scrapper and 128 jts. Tag stringer of cement at 3,965. Rig up power swivel and drilling equipment. Clean out cement to 4,136'. Circulate hole clean for 1/2 hr. Pull out of hole with 4 jts. Drain up equipment.

14. I hereby certify that the foregoing is true and correct

Signed Susan Sachitana Title

Susan H. Sachitana

Regulatory Specialist

Date

November 23, 1994

(This space for Federal or State office use)

Approved by _____ Title _____

Date _____

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

RECEIVED

DEC 5 1994

FORM APPROVED

BUDGET BUREAU NO. 1004-0135

PIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or to open a new well in a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals.

5. Lease Designation and Serial No.

U-01790

6. If Indian, Allottee or Tribe Name

SUBMIT IN TRIPLICATE

1. Type of Well

[] Oil Well [X] Gas Well [] Other

7. If Unit or CA, Agreement Designation
River Bend Unit

2. Name of Operator

CNG PRODUCING COMPANY

8. Well Name and No.

8-11F

3. Address and Telephone No.

CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000

9. API Well No.

43-047-32512

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

Surface 500' FEL & 1,800' FNL of Sec. 11-T10S-R20E

10. Field and Pool, or Exploratory Area
Island11. County or Parish, State
Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

[] Notice of Intent

[X] Subsequent Report

[] Final Abandonment Notice

TYPE OF ACTION

[] Abandonment

[] Recompletion

[] Plugging Back

[] Casing Repair

[] Altering Casing

[X] Other - Weekly Report

[] Change of Plans

[] New Construction

[] Non-Routine Fracturing

[] Water Shut-Off

[] Conversion to Injection

[] Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

CONFIDENTIAL

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

November 24, 1994 - December 2, 1994

No pressure on well. Run in hole with 4 jts. Rig up drilling equipment. Begin drilling out cement from 4,136' to 4,258'. Hard cement fell through. Run in hole to 4,290'. Circulate hole clean. Run in hole to 4,298'. Tag sand. Pull up to 4,290'. Pressure test squeeze to 500 PSI. Tested OK. Rig down drilling equipment. Pull out of hole.

Lay down bit and casing scrapper. Pull up. Run in hole with 130 jts to 4,040'. Shut in well. Drain equipment.

No pressure on well. Run in hole with 8 jts. Circulate frac balls and sand off bridge plug at 4,310'. Pull out of hole. Lay down bridge plug. Run in hole with rotating head. Tag sand at 4,855'. Clean out sand to bridge plug at 5,000'. Release bridge plug. Circulate gas out for 1 1/2 hrs. Pull out of hole with 40 jts. Drain equipment.

Bled off pressure. Circulate well for 1 hour. Control well. Pull out of hole with tubing and bridge plug. Run in hole with rotating head and tubing. Tag sand at 5,742'. Clean out sand to 5,820'. Circulate hole clean. Release bridge plug. Hole went on vacuum. Pull out of hole with 60 jts. Drain equipment. Well had 300 PSI on casing and 0 PSI on tubing. Controlled well with 80 bbls. Pull out of hole with bridge plug. Well started flowing when tripped out of hole. Pumped 50 bbls down casing. Control well. Run in hole with rotating head and 193 jts. Tag sand at 5,958'. Rig up pump line. Pump 430 bbls to break circulation. Clean out sand from 5,938' to 6,050'. Circulate hole clean. Release bridge plug. Pull out of hole with 70 jts. Drain up equipment.

14. I hereby certify that the foregoing is true and correct

Signed

Susan H. Sachitana

Title

Regulatory Specialist

Date

December 2, 1994

(This space for Federal or State office use)

Approved by

Title

Date

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
BUDGET BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Designation River Bend Unit
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 8-11F
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No. 43-047-32512
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface 500' FEL & 1,800' FNL of Sec. 11-T10S-R20E	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION


☐ Notice of Intent☐ Abandonment☐ Change of Plans☒ Subsequent Report☐ Recompletion☐ New Construction☐ Final Abandonment Notice☐ Plugging Back☐ Non-Routine Fracturing☐ Casing Repair☐ Water Shut-Off☐ Altering Casing☐ Conversion to Injection☒ Other - Initial Production☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

Well was placed on initial production on December 15, 1994 at 12:30 PM.

CONFIDENTIAL



14. I hereby certify that the foregoing is true and correct

Signed Susan Sachitana Title Regulatory Specialist Date December 19, 1994
Susan H. Sachitana

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT(See other in-
structions on
reverse side)

Expires August 31, 1995

WELL COMPLETION OR RECOMPLETION REPORT AND LOG*

1a. TYPE OF WELL:		OIL WELL <input type="checkbox"/>	GAS WELL <input type="checkbox"/>	DRY <input checked="" type="checkbox"/>	Other <input type="checkbox"/>	5. LEASE DESIGNATION AND SERIAL NO. U-1790	
1b. TYPE OF COMPLETION:		NEW WORK WELL <input checked="" type="checkbox"/>	DEEP-EN <input type="checkbox"/>	PLUG BACK <input type="checkbox"/>	DIFF. RESVR <input type="checkbox"/>	Other <input type="checkbox"/>	6. IF INDIAN, ALLOTTEE OR TRIBE NAME RBU
2. NAME OF OPERATOR CNG Producing Company						7. UNIT AGREEMENT NAME River Bend Unit	
3. ADDRESS OF OPERATOR CNG Tower - 1450 Poydras St., New Orleans, LA 70112-6000						8. FARM OR LEASE NAME RBU	
4. LOCATION OF WELL (Report location clearly and in accordance with any title GAS & MINING)						9. WELL NO. 8-11F	
At surface 500' FEL & 1,800' FNL of Sec. 11-T10S-R20E						10. FIELD AND POOL, OR WILDCAT Natural Buttes	
At top prod. interval reported below						11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA SE of NE of 11-T10S-R20E	
At total depth						12. COUNTY OF 13. STATE Parish Utah	
14. PERMIT NO. 43-047-32512		DATE ISSUED 06/03/94		15. DATE SPUDDED 08/02/94		16. DATE T.D. REACHED 09/01/94	
17. DATE COM. (Ready to prod.) 12/02/94		18. ELEVATION (OF RKB, RT, GR, ETC.)* 5,043' GR		19. ELEV. CASINGHEAD		20. TOTAL DEPTH MD & TVD 7,000'	
21. PLUG, BACK T.D. MD & TVD 6,426'		22. IF MULTIPLE COMPL., HOW MANY* 5 Zones		23. INTERVALS DRILLED BY ROTARY TOOLS CABLE TOOLS Rotary		24. PRODUCING INTERVAL(S), OF THIS COMPLETION - TOP, BOTTOM, NAME (MD AND TVD)* 6,734-52', 6,304-70', 5,944-64', 5,726-44' & 4,838-52' - Wasatch	
25. TYPE ELECTRIC AND OTHER LOGS RUN DLL, Density/Neutron, Gamma Ray, Caliper 9-6-94						26. WAS WELL CORED No	
27. CASING RECORD (Report all strings set in well)							
CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD		AMOUNT PULLED	
8 5/8"	24#	378'	12 1/4"	224 sks 25/75 Pozmix with 2% Calc2 and .25#/sk D-29 flake.			
5 1/2"	17# N-80	6,518'	6-1/2"	380 sks Hi-Lift cement, 12% D-20, 1% D-79, 1% D-112, 3% 10#/sk D-42, .25#/sk D-29, 2% D-46 followed by 760 sks 10-1			
28. LINER RECORD							
SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	30. TUBING RECORD		
					SIZE	DEPTH SET (MD)	PACKER SET (MD)
					2 3/8"	4,322'	
31. PERFORATION RECORD (Interval, size and number)				32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.			
Zone #1 - 6,134-52' & 6,304-10'				DEPTH INTERVAL (MD)			
Zone #2 - 5,944-64'				AMOUNT AND KIND OF MATERIAL USED			
Zone #3 - 5,726-44'				Zone #1 140,000 lbs of 20/40 Frac Sand			
Zone #4 - 4,838-52'				Zone #2 211,500 lbs of 20/40 Frac Sand			
Zone A - 4,236-48' & 4,252-58'				Zone #3 156,660 lbs of 20/40 Frac Sand			
				Zone #4 127,320 lbs of 20/40 Frac Sand			
				Zone A 3,000 gallons of 15% HCL Acid & 60 7/8" ball sealer.			
33. PRODUCTION							
DATE FIRST PRODUCTION 12/15/94		PRODUCTION MET (Flowing, gas lift, pumping - size and type of pump) Flowing			WELL STATUS (Producing or shut-in) Producing		
DATE OF TEST 12/15/94	HOURS TESTED 22	CHOKER SIZE 14/64	PROD'N FOR TEST PERIOD ----->	OIL-BBL. -	GAS-MCF. 215	WATER-BBL. -	GAS-OIL RATIO -
FLOW. TUBING PRESS. 1200	CASING PRESSURE 1200	CALCULATED 24 HR RATE ----->	OIL-BBL. -	GAS-MCF. 235	WATER-BBL. -	OIL GRAVITY-API (CORR.) -	
34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.) Sold						TEST WITNESSED BY Mitch Hall	
35. LIST OF ATTACHMENTS							
36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.							

SIGNED

W. Scott Childress

TITLE Supervisor, Prod. Eng.

DATE 12/29/94

*(See Instruction and Spaces for Additional Data on Reverse Side)

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof, cored intervals; and all drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries)

38. GEOLOGICAL MARKERS

FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	TOP	
					MEAS. DEPTH	TRUE VERT. DEPTH
Wasatch	4,836'	4,856'	sandstone, gy-wh, vfgr-fgr, sa-sr, calcareous, tite	Wasatch Tongue	4,280'	4,280'
Wasatch	5,726'	5,744'	aa	Green River Tongue	4,608'	4,608'
Wasatch	5,934'	5,982'	aa	Wasatch	4,750'	4,750'
Wasatch	6,134'	6,152'	aa			

CONFIDENTIAL

WELL: 8-11F
FIELD: RBU
SECTION: 11,T10S,R20E
COUNTY: UINTAH
STATE: UTAH
ELEVATION: 5043'
KB TO FLANGE: 15'
INPUT DATE: 12/1/94
ENGINEER: WSC
COMPLETION DATE: 12/2/94

CNG PRODUCING
NEW ORLEANS

RECEIVED
JAN 3 1995

DIVISION OF
OIL, GAS & MINING

CONFIDENTIAL

CURRENT

TUBING: 2 3/8"

ZONE A
POTENTIAL OIL

= 4236-48

4252-58

TESTED WET - SQUEEZED 50 SXS.

OTIS HYD PACKER @ 4322'

= ZONE NO. 4

4838-52

127M #'S - BORATE

FCP - 400 PSI - WET GAS & YELLOW OIL

= ZONE NO. 3

5726-44

156M #'S - BORATE

FCP - 260 PSI - 500 M/D

= ZONE NO. 2

5944-64

211M #'S - BORATE

FCP - 25 PSI - 50 M/D

= ZONE NO.1

6134-52

6304-10

140M #'S - BORATE

1/4" WATER - NO GAS

SN @ 6089'

EOT @ 6090'

PBTD @ 6390'

5 1/2" CASING @ 6500'

UTAH DIVISION OF OIL, GAS AND MINING EQUIPMENT INVENTORY

Operator: CNG Producing Co. Lease: State: Federal: ☒ Indian: Fee:

Well Name: RBU 8-11 F API Number: 43-047-32512

Section: 11 Township: 10S Range: 20E County: Uintah Field: Natural Buttes

Well Status: P6W Well Type: Oil: Gas: ☒

PRODUCTION LEASE EQUIPMENT: ☒ CENTRAL BATTERY:

<input checked="" type="checkbox"/> Well head	<u> </u> Boiler(s)	<u> </u> Compressor	<u> </u> Separator(s)
<input checked="" type="checkbox"/> Dehydrator(s)	<input checked="" type="checkbox"/> Shed(s)	<u> </u> Line Heater(s)	<input checked="" type="checkbox"/> Heated Separator
<u> </u> VRU	<u> </u> Heater Treater(s)		

PUMPS:

 Triplex Chemical Centrifugal

LIFT METHOD:

 Pumpjack Hydraulic Submersible ☒ Flowing

GAS EQUIPMENT:

☒ Gas Meters Purchase Meter ☒ Sales Meter

TANKS: NUMBER

SIZE

<u> </u> 1 Oil Storage Tank(s)	<u> </u> 300	BBLS
<u> </u> Water Tank(s)	<u> </u>	BBLS
<u> </u> Power Water Tank	<u> </u>	BBLS
<u> </u> Condensate Tank(s)	<u> </u>	BBLS
<u> </u> Propane Tank	<u> </u>	

REMARKS: All fluids go to production tank. Tank
has a burner

Location central battery: Qtr/Qtr: Section: Township: Range:

Inspector: David W. Haeffner Date: 1/20/95

CNG

RBU 8-1/E

43-047-32512

North
↑

Access

Berm

300
Bbl.
Production
Tank

wellhead



Heated Separator
Recorder
Dehydrator

Gas Sales
Line

Recharge
Pit

Top
Soil

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
EXPIRES: July 31, 1996

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instruction on reverse side


1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. U-1790
2. Name of Operator CNG PRODUCING COMPANY		6. If Indian, Allottee or Tribe Name
3a. Address 1450 POYDRAS ST, NEW ORLEANS, LA 70112-6000	3b. Phone No. (include area code) (504) 593-7000	7. If Unit or CA/ Agreement, Name and/or No. RIVER BEND UNIT
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 500' FEL & 1,800' FNL of Sec. 11-T10S-R20E		8. Well Name and No. 8-11F
		9. API Well No. 43-047-32512
		10. Field and Pool, or Exploratory Area NATURAL BUTTES 630
		11. County or Parish, State UINTAH, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize <input type="checkbox"/> Deepen <input type="checkbox"/> Production (Start/Resume) <input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing <input type="checkbox"/> Fracture Treat <input type="checkbox"/> Reclamation <input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair <input type="checkbox"/> New Construction <input type="checkbox"/> Recomplete <input checked="" type="checkbox"/> Other PLUNGER LIFT
	<input type="checkbox"/> Change Plans <input type="checkbox"/> Plug and Abandonment <input type="checkbox"/> Temporarily Abandon
	<input type="checkbox"/> Convert to Injection <input type="checkbox"/> Plug Back <input type="checkbox"/> Water Disposal

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation have been completed, and the operator has determined that the site is ready for final inspection.)

Installed plunger lift equipment on above well. Well on plunger as of 11/26/97.



14. I hereby certify that the forgoing is true and correct Name (Printed/Typed) SUSAN H. SACHITANA		Title COORDINATOR, REGULATORY REPORTS
Signature <i>Susan H. Sachitana</i>		Date 980120
THIS SPACE FOR FEDERAL OR STATE OFFICE USE		
Approved by	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.		Office
Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.		



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

In Reply Refer To:
3100
U-01470-A et al
(UT-932)

JUN 2 2000

NOTICE

Dominion Exploration & Production, Inc. : Oil and Gas Leases
1450 Poydras Street :
New Orleans, LA 70112-6000 :

Name Change Recognized

Acceptable evidence has been received in this office concerning the change of name of CNG Producing Company to Dominion Exploration & Production, Inc. on Federal oil and gas leases.

The oil and gas lease files identified on the enclosed exhibit have been noted as to the name change. The exhibit was compiled from your list of leases and a list of leases obtained from our automated records system. We have not abstracted the lease files to determine if the entity affected by the name change holds an interest in the leases identified nor have we attempted to identify leases where the entity is the operator on the ground maintaining no vested record title or operating rights interests. We are notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the name change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

The following lease on your list is closed on the records of this office: U-029277.

Due to the name change, the name of the principal on the bond is required to be changed from CNG Producing Company to Dominion Exploration & Production, Inc. on Bond No. 524 7050 (BLM Bond No. WY1898). You may accomplish this name change either by consent of the surety on the original bond or by a rider to the original bond. Otherwise, a replacement bond with the new name should be furnished to the Wyoming State Office.

/s/ Robert Lopez

Robert Lopez
Chief, Branch of
Minerals Adjudication

Enclosure
Exhibit of Leases

RECEIVED

JUN 05 2000

DIVISION OF
OIL, GAS AND MINERAL

cc: Wyoming State Office
New Mexico State Office
Moab Field Office
Vernal Field Office
MMS—Reference Data Branch, MS 3130, Box 5860, Denver, CO 80217
State of Utah, DOGM, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC, UT 84114-5801
Irene Anderson (UT-932)
Teresa Thompson (UT-931)
LaVerne Steah (UT-942)

Dominion Exploration & Production, Inc.
1450 Poydras Street, New Orleans, LA 70112-6000
Phone: 504-593-7000



June 27, 2000

Mr. Jimmy Thompson
Utah Board of Oil Gas & Mining
1594 West North Temple
Suite 1210
Salt Lake City, UT 84114-5801

RE: Name Change Documentation for CNG Producing Company

Dear Mr. Thompson:

CNG Producing Company has become Dominion Exploration & Production, Inc. effective April 12, 2000. Enclosed please find a sundry regarding the name change with an attached listing of all the permits in the name of CNG Producing Company to be changed to Dominion Exploration & Production, Inc. Also enclosed please find a Form UIC 5 for the Transfer of Authority to Inject for the Federal #1-26B well.

If you have any questions or require any additional information, please contact me at (504) 593-7260.

Sincerely,

DOMINION EXPLORATION & PRODUCTION, INC.

Susan H. Sachitana
Regulatory Reports Administrator

Enclosure

cc: Nelda Decker

RECEIVED

JUN 29 2000

**DIVISION OF
OIL, GAS AND MINING**

STATE OF UTAH
DIVISION OF OIL, GAS & MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells or to reenter plugged and abandoned wells.

Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well : OIL <input type="checkbox"/> GAS <input type="checkbox"/> OTHER:	5. Lease Designation and Serial Number: VARIOUS
2. Name of Operator: DOMINION EXPLORATION & PRODUCTION, INC.	6. If Indian, Allottee or Tribe Name:
3. Address and Telephone Number: 1460 Poydras Street, New Orleans, LA 70112-6000 (504) 593-7260	7. Unit Agreement Name:
4. Location of Well Footages: QQ, Sec. T., R., M.:	8. Well Name and Number: VARIOUS
	9. API Well Number
	10. Field and Pool, or Wildcat: Natural Buttes 630
	County: UTAH State: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA	
NOTICE OF INTENT (SUBMIT IN DUPLICATE)	SUBSEQUENT REPORT (Submit Original Form Only)
<input type="checkbox"/> Abandon <input type="checkbox"/> Repair Casing <input type="checkbox"/> Change of Plans <input type="checkbox"/> Convert to Injection <input type="checkbox"/> Fracture Treat or Acidize <input type="checkbox"/> Multiple Completion <input type="checkbox"/> Other	<input type="checkbox"/> Abandon* <input type="checkbox"/> Repair Casing <input type="checkbox"/> Change of Plans <input type="checkbox"/> Convert to Injection <input type="checkbox"/> Fracture Treat or Acidize <input checked="" type="checkbox"/> Other
<input type="checkbox"/> New Construction <input type="checkbox"/> Pull or Alter Casing <input type="checkbox"/> Recomplete <input type="checkbox"/> Reperforate <input type="checkbox"/> Vent or Flare <input type="checkbox"/> Water Shut-Off	<input type="checkbox"/> New Construction <input type="checkbox"/> Pull or Alter Casing <input type="checkbox"/> Reperforate <input type="checkbox"/> Vent or Flare <input type="checkbox"/> Water Shut-Off OPERATOR NAME CHANGE FOR WELLS
Approximate date work will start _____	Date of work completion _____
	Report results of Multiple Completion and Recompletion to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.
	*Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETION OPERATIONS (Clearly State all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Please be advised that effective April 12, 2000, CNG Producing Company has changed its name to Dominion Exploration & Production, Inc. and would like to transfer the well permits into the name of Dominion Exploration & Production, Inc. Our new bond has been filed and is pending approval with the State of Utah. The bond number is 76S 63050 361.



 John R. Lewis

Sr. Vice-President - CNG Producing Company

RECEIVED

JUN 29 2000

DIVISION OF
OIL, GAS AND MINING

13.	
Name & Signature:  John R. Lewis	Title: Sr. Vice-President - Dominion Expl. & Prod., Inc. Date: June 26, 2000

(This space for State use only)



State of Utah

DEPARTMENT OF COMMERCE

Division of Corporations & Commercial Code

Application To Amend The CERTIFICATE OF AUTHORITY OR REGISTRATION of

CNG Producing Company
Business Entity Name

Delaware
Name of Home State

5528914
CO 106990
File Number

Check Appropriate Box	
<input checked="" type="checkbox"/>	Foreign Profit Corporation \$35.00
<input type="checkbox"/>	Foreign Non-Profit Corporation \$35.00
<input type="checkbox"/>	Foreign Limited Partnership \$25.00
<input type="checkbox"/>	Foreign Limited Liability Company \$35.00

I. AMENDING THE BUSINESS NAME

The business name is changed to: Dominion Exploration & Production, Inc.

The corporation shall use as its name in Utah: Dominion Exploration & Production, Inc.

(The corporation shall use its name as set forth on #1, unless this name is not available)

NOTE: If the business name has changed its name in the home state, a copy of the Certificate of Amendment or a certified copy of the amendment must accompany this application.

Check the following:

- ☒ The name of the corporation is changing its name in Utah to the new name of the corporation in the home state.
☐ The name of the corporation is being changed in Utah to comply with Utah State Insurance Regulations.

II. AMENDING THE DURATION OF THE BUSINESS EXISTENCE

The businesses period of duration is changed to: _____

III. AMENDING THE STATE OR COUNTRY OF INCORPORATION/REGISTRATION

The corporation's state or country of incorporation/registration is changed to: _____

IV. Other:

(Limited Partnership changing General Partners, Limited Companies changing Members or Managers, Change of statement who is managing, etc.)
 Use an attached sheet if needed.

Under penalties of perjury, I declare this Application to Amend the Certificate of Authority or Registration to be, to the best of my knowledge and belief, true and correct.

Signature

Vice President & Corporate Secretary
 Title

April 20, 2000
 Date

State of Utah
 Department of Commerce
 Division of Corporations and Commercial Code

I hereby certify that the foregoing has been filed and approved on this 25 day of April, 2000 in the office of this Division and hereby issue this Certificate thereof.

Examiner

Date



LEON JENSEN
 Director

Date: 04/25/2000

Receipt Number: 22156

Amount Paid: \$60.00

STATE OF UTAH
 DIVISION OF CORPORATIONS
 AND COMMERCIAL CODE
 160 East 300 South / Box 146705
 Salt Lake City, UT 84114-6705
 Service Center: (801) 530-4849

Web Site: <http://www.commerce.state.ut.us>

FILED

APR 25 2000

EXHIBIT A
OIL & GAS LEASES AFFECTED BY THE NAME CHANGE

U-01470-A	U-017713	U-46825
U-01790	U-035316	U-62232
U-02896-A	U-037164	UTU-66743
U-03505	U-0143519	UTU-68108
U-03576	U-0143520-A	UTU-68388
U-013429-A	U-0143521-A	UTU-68625
U-013765	U-0147541	UTU-69166
U-013766	U-0147541-A	UTU-73011
U-013767	U-3405	UTU-73433
U-013769	U-7206	UTU-76499
U-013769-A	U-9803	UTU-76500
U-013769-B	U-10291	UTU-76717
U-013769-C	U-16544	UTU-76718
U-013792	U-19266	
U-013793	U-28203	U-60759 (CA)
U-013793-A	U-29784	U-60940 (CA)
U-013794	U-30693	UTU-77360 (CA)
U-013818-A	U-37246	U-63054X (River Bend)
U-013820	U-39221	UTU-73218X
U-013821-A	U-43156	(West Willow Creek Unit)

api	well_name	well_status_main	lease_num
4304732111	RBU 7-15F	LA	14-20-H62-2645
4304732189	RBU 13-10F	P	14-20-H62-2645
4304730768	RBU 7-22F	P	14-20-H62-2646
4304732109	RBU 15-15F	LA	14-20-H62-2646
4304732844	RBU 15-15F	P	14-20-H62-2646
4304732269	RBU 4-15F	PA	INDIAN
4304733360	RBU 1-16F	DRL	ML-3393
4304731980	STATE 2-36E	LA	ML-42175
4304731801	RIVER BEND U 2-10D	S	U-013429-A
4304731551	RBU 10X-15E	PA	U-013760
4304731716	RIVER BEND U 7-13E	LA	U-013765
4304731718	RBU 15-13E	LA	U-013765
4304732600	RBU 1-21EO	P	U-013766
4304733033	RBU 7-23E	P	U-013766
4304733160	RBU 8-15E	P	U-013766
4304733272	RBU 13-3F	P	U-013767
4304733366	RBU 5-18F	P	U-013769
4304732991	RBU 6-19F	P	U-013769-A
4304733157	RBU 7-19F	P	U-013769-A
4304732454	RBU 9-14EO	P	U-013792
4304732514	RBU 8-14EO	LA	U-013792
4304732678	RBU 13-22EO	LA	U-013792
4304732989	RBU 13-10E	P	U-013792
4304733156	RBU 4-14E	P	U-013792
4304733161	RBU 16-10E	P	U-013792
4304733194	RBU 2-14E	P	U-013792
4304733365	RBU 12-14E	P	U-013792
4304732990	RBU 13-18F2	P	U-013793
4304732396	RBU 3-21F	P	U-013793-A
4304732407	RBU 15-14F	P	U-013793-A
4304732408	RBU 4-23F	P	U-013793-A
4304732899	RBU 3-14F	P	U-013793-A
4304732900	RBU 8-23F	P	U-013793-A
4304732972	RBU 1-21F	P	U-013793-A
4304733087	RBU 6-23F	P	U-013793-A
4304733158	RBU 7-20F	P	U-013793-A
4304733424	RBU 5-20F	P	U-013793-A
4304732392	RBU 11-14F	P	U-013793A
4304731719	RBU 5-24E	LA	U-013794
4304732483	RBU 5-24EO	P	U-013794
4304733034	RBU 9-18F	P	U-013794
4304733159	RBU 7-24E	P	U-013794
4304731352	RBU 16-3D	P	U-013820
4304733599	RBU 1-1D	APD	U-013820
4304733090	RBU 11-22F	P	U-0143519
4304733089	RBU 8-22F	P	U-0143521
4304732901	RBU 12-23F	P	U-01470-A
4304733091	RBU 16-22F	P	U-01470-A
4304733368	RBU 14-23F	P	U-01470-A
4304731138	RBU 11-34B	P	U-017713
4304731724	RBU 11-35B	S	U-017713
4304732094	RBU 13-35B	P	U-017713
4304732222	RBU 15-35B	S	U-017713
4304730585	RBU 7-11F	P	U-01790
4304732512	RBU 8-11F	P	U-01790
4304731739	RBU 9-9E	P	U-03505
4304732415	RBU 3-10EX (RIG SKID)	P	U-035316
4304733035	RBU 14-19F	P	U-13769-A
4304731881	APACHE 12-25	S	U-3405
4304732417	FEDERAL 3-25B	P	U-39221
4304731782	SADDLE TREE DRAW 13-34	LA	U-57598
4304732934	RBU 3-10F	P	U-7206
4304732969	RBU 11-10F	P	U-7206
4304732970	RBU 12-15F	P	U-7206
4304732971	RBU 15-16F	P	U-7206

OPERATOR CHANGE WORKSHEET

Check each listed item when completed. Write N/A if item is not applicable.

<input type="checkbox"/>	4-KAS
2-CDW <input checked="" type="checkbox"/>	5-SJ <input checked="" type="checkbox"/>
3-JLT	6-FILE

Change of Operator (Well Sold)

Designation of Agent

X Operator Name Change Only

Merger

The operator of the well(s) listed below has changed, effective: 4-12-00TO:(New Operator) DOMINION EXPL & PROD INC.FROM:(Old Operator) CNG PRODUCING COMPANYAddress: 1450 POYDRAS STREET
NEW ORLEANS, LA 70112-6000Address: 1450 POYDRAS STREET
NEW ORLEANS, LA 70112-6000Phone: 1-(504)-593-7000Phone: 1-(504)-593-7000Account No. N1095Account No. N0605

WELL(S):	CA Nos.	or	RIVER BEND	Unit
Name: <u>RBW 1-21F</u>	API: <u>43-047-32972</u>	Entity: <u>7050</u>	S <u>21</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-013793-A</u>
Name: <u>RBW 6-23F</u>	API: <u>43-047-33087</u>	Entity: <u>7050</u>	S <u>23</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-013793-A</u>
Name: <u>RBW 5-20F</u>	API: <u>43-047-33424</u>	Entity: <u>7050</u>	S <u>20</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-013793-A</u>
Name: <u>RBW 11-14F</u>	API: <u>43-047-32392</u>	Entity: <u>7050</u>	S <u>14</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-013793-A</u>
Name: <u>RBW 9-18F</u>	API: <u>43-047-33034</u>	Entity: <u>7050</u>	S <u>18</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-013794</u>
Name: <u>RBW 7-24E</u>	API: <u>43-047-33159</u>	Entity: <u>7050</u>	S <u>24</u> T <u>10S</u> R <u>19E</u>	Lease: <u>U-013794</u>
Name: <u>RBW 16-3D</u>	API: <u>43-047-31352</u>	Entity: <u>7070</u>	S <u>03</u> T <u>10S</u> R <u>18E</u>	Lease: <u>U-013820</u>
Name: <u>RBW 11-22F</u>	API: <u>43-047-33090</u>	Entity: <u>7050</u>	S <u>22</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-0143519</u>
Name: <u>RBW 8-22F</u>	API: <u>43-047-33089</u>	Entity: <u>7050</u>	S <u>22</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-0143521</u>
Name: <u>RBW 12-23F</u>	API: <u>43-047-32901</u>	Entity: <u>7050</u>	S <u>23</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-01470-A</u>
Name: <u>RBW 16-22F</u>	API: <u>43-047-33091</u>	Entity: <u>7050</u>	S <u>22</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-01470-A</u>
Name: <u>RBW 14-23F</u>	API: <u>43-047-33368</u>	Entity: <u>7050</u>	S <u>23</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-01470-A</u>
Name: <u>RBW 8-11F</u>	API: <u>43-047-32512</u>	Entity: <u>7050</u>	S <u>11</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-01790</u>
Name: <u>RBW 9-9E</u>	API: <u>43-047-31739</u>	Entity: <u>7050</u>	S <u>09</u> T <u>10S</u> R <u>19E</u>	Lease: <u>U-03505</u>
Name: <u>RBW 3-10EX</u>	API: <u>43-047-32415</u>	Entity: <u>7050</u>	S <u>10</u> T <u>10S</u> R <u>19E</u>	Lease: <u>U-035316</u>
Name: <u>RBW 14-19F</u>	API: <u>43-047-33035</u>	Entity: <u>7050</u>	S <u>19</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-13769-A</u>
Name: <u>RBW 3-10F</u>	API: <u>43-047-32934</u>	Entity: <u>7050</u>	S <u>10</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-7206</u>
Name: <u>RBW 11-10F</u>	API: <u>43-047-32969</u>	Entity: <u>7050</u>	S <u>10</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-7206</u>
Name: <u>RBW 12-15F</u>	API: <u>43-047-32970</u>	Entity: <u>7050</u>	S <u>15</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-7206</u>
Name: <u>RBW 15-16F</u>	API: <u>43-047-32971</u>	Entity: <u>7050</u>	S <u>16</u> T <u>10S</u> R <u>20E</u>	Lease: <u>U-7206</u>

OPERATOR CHANGE DOCUMENTATION

- YES 1. A pending operator change file has been set up.
- YES 2. (R649-8-10) Sundry or other legal documentation has been received from the **FORMER** operator on 6-29-00.
- YES 3. (R649-8-10) Sundry or other legal documentation has been received from the **NEW** operator on 6-29-00.
- YES 4. The new company has been looked up in the **Department of Commerce, Division of Corporations Database** if the new operator above is not currently operating any wells in Utah. Is the operator registered with the State? **Yes/No** If yes, the company file number is SEE ATTACHED. If no, Division letter was mailed to the new operator on _____.

- YES 5. **Federal and Indian Lease Wells.** The BLM or the BIA has approved the merger, **name change** or operator change for all wells listed above involving Federal or Indian leases on 6-2-00.
- N/A 6. **Federal and Indian Units.** The BLM or the BIA has approved the successor of unit operator for all wells listed above involving unit operations on _____.
- N/A 7. **Federal and Indian Communitization Agreements ("CA").** The BLM or the BIA has approved the operator change for all wells listed above involved in the CA on _____.
- N/A 8. **Underground Injection Control ("UIC") Program.** The Division has approved UIC Form 5, Transfer of Authority to Inject, for the enhanced/secondary recovery unit/project and/or for the water disposal well(s) listed above.
- YES 9. Changes have been entered in the **Oil and Gas Information System** for each well listed on 8-1-00.
- YES 10. Changes have been included on the **Monthly Operator Change letter** on 8-1-00.

STATE BOND VERIFICATION

- N/A 1. State Well(s) covered by Bond No. _____.

FEE WELLS - BOND VERIFICATION / LEASE INTEREST OWNER NOTIFICATION

- N/A 1. (R649-3-1) The **NEW** operator of any fee lease well(s) listed above has furnished a proper bond.
- N/A 2. A **copy of this form** has been placed in the **new and former operator's bond files** on _____.
- N/A 3. The **FORMER** operator has requested a release of liability from their bond as of todays date _____? If yes, Division response was made to this request by letter dated _____. (see bond file).
- N/A 4. (R649-2-10) The **Former** operator of any Fee lease wells listed above has been contacted and informed by letter dated _____, of their responsibility to notify all interest owners of this change.
- N/A 5. Bond information added to **RBDMS** on _____.
- N/A 6. Fee wells attached to bond in **RBDMS** on _____.

FILMING

- ____ 1. All attachments to this form have been **microfilmed** on 2.23.01.

FILING

- ____ 1. **Originals/Copies** of all attachments pertaining to each individual well have been filed in each **well file**.
- ____ 2. The **original of this form** has been filed in the operator file and a copy in the old operator file.

COMMENTS

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

ROUTING

1. DJJ
2. CDW

X - Change of Operator (Well Sold)

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:

7/1/2007

FROM: (Old Operator): N1095-Dominion Exploration & Production, Inc 14000 Quail Springs Parkway, Suite 600 Oklahoma City, OK 73134 Phone: 1 (405) 749-1300	TO: (New Operator): N2615-XTO Energy Inc 810 Houston St Fort Worth, TX 76102 Phone: 1 (817) 870-2800
--	--

CA No.				Unit:		RIVER BEND				
WELL NAME		SEC		TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
SEE ATTACHED LIST										

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 8/6/2007
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 8/6/2007
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 8/6/2007
- a. Is the new operator registered in the State of Utah: Business Number: 5655506-0143
- b. If **NO**, the operator was contacted on: _____
- a. (R649-9-2) Waste Management Plan has been received on: IN PLACE
- b. Inspections of LA PA state/fee well sites complete on: n/a
- c. Reports current for Production/Disposition & Sundries on: ok
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM BIA
- Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: _____
- Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: _____
- Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: _____

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 9/27/2007
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 9/27/2007
- Bond information entered in RBDMS on: 9/27/2007
- Fee/State wells attached to bond in RBDMS on: 9/27/2007
- Injection Projects to new operator in RBDMS on: 9/27/2007
- Receipt of Acceptance of Drilling Procedures for APD/New on: 9/27/2007

BOND VERIFICATION:

- Federal well(s) covered by Bond Number: UTB000138
 - Indian well(s) covered by Bond Number: n/a
 - a. (R649-3-1) The **NEW** operator of any state/fee well(s) listed covered by Bond Number 104312762
 - b. The **FORMER** operator has requested a release of liability from their bond on: 1/23/2008
- The Division sent response by letter on: _____

LEASE INTEREST OWNER NOTIFICATION:

- (R649-2-10) The **NEW** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: _____

COMMENTS:

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER:
2. NAME OF OPERATOR: XTO Energy Inc. <i>N2615</i>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 810 Houston Street CITY Fort Worth STATE TX ZIP 76102		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: SEE ATTACHED		8. WELL NAME and NUMBER: SEE ATTACHED
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		9. API NUMBER: SEE ATTACHED
COUNTY: Uintah		10. FIELD AND POOL, OR WILDCAT: Natural Buttes
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective July 1, 2007, XTO Energy Inc. has purchased the wells listed on the attachment from:

Dominion Exploration & Production, Inc.
14000 Quail Springs Parkway, Suite 600
Oklahoma City, OK 73134

N1095

James D. Abercrombie
James D. Abercrombie
Sr. Vice President, General Manager - Western Business Unit
(405) 749-1300

Please be advised that XTO Energy Inc. is considered to be the operator on the attached list and is responsible under the terms and conditions of the lease for the operations conducted upon the lease lands. Bond coverage is provided by Nationwide BLM Bond #104312750 and Department of Natural Resources Bond #104312762.

NAME (PLEASE PRINT) <u>Edwin S. Ryan, Jr.</u>	TITLE <u>Sr. Vice President - Land Administration</u>
SIGNATURE <i>Edwin S. Ryan, Jr.</i>	DATE <u>7/31/2007</u>

(This space for State use only)

APPROVED 9127107

Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

(See Instructions on Reverse Side)

RECEIVED

AUG 06 2007

DIV. OF OIL, GAS & MINING

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304730087	OSCU 2	NWSE	03	100S	200E	U-037164	7050	Federal	GW	P
4304730266	RBU 11-18F	NESW	18	100S	200E	U-013793	7050	Federal	GW	P
4304730374	RBU 11-13E	NESW	13	100S	190E	U-013765	7050	Federal	GW	P
4304730375	RBU 11-15F	NESW	15	100S	200E	U-7206	7050	Federal	GW	P
4304730376	RBU 7-21F	SWNE	21	100S	200E	U-013793-A	7050	Federal	GW	P
4304730405	RBU 11-19F	NESW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304730408	RBU 11-10E	NESW	10	100S	190E	U-013792	7050	Federal	GW	P
4304730410	RBU 11-14E	NESW	14	100S	190E	U-013792	7050	Federal	GW	P
4304730411	RBU 11-23E	NESW	23	100S	190E	U-013766	7050	Federal	GW	P
4304730412	RBU 11-16F	NESW	16	100S	200E	U-7206	7050	Federal	GW	P
4304730585	RBU 7-11F	SWNE	11	100S	200E	U-01790	7050	Federal	GW	P
4304730689	RBU 11-3F	NESW	03	100S	200E	U-013767	7050	Federal	GW	P
4304730720	RBU 7-3E	SWNE	03	100S	190E	U-013765	7050	Federal	GW	P
4304730759	RBU 11-24E	NESW	24	100S	190E	U-013794	7050	Federal	GW	P
4304730761	RBU 7-10F	SWNE	10	100S	200E	U-7206	7050	Federal	GW	P
4304730762	RBU 6-20F	SENE	20	100S	200E	U-013793-A	7050	Federal	GW	P
4304730768	RBU 7-22F	SWNE	22	100S	200E	14-20-H62-2646	7050	Indian	GW	P
4304730887	RBU 16-3F	SESE	03	100S	200E	U-037164	7050	Federal	GW	P
4304730915	RBU 1-15E	NENE	15	100S	190E	U-013766	7050	Federal	GW	P
4304730926	RBU 1-14E	NENE	14	100S	190E	U-013792	7050	Federal	GW	P
4304730927	RBU 1-22E	NENE	22	100S	190E	U-013792	7050	Federal	GW	P
4304730970	RBU 1-23E	NENE	23	100S	190E	U-013766	7050	Federal	GW	P
4304730971	RBU 4-19F	NWNW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304730973	RBU 13-11F	SWSW	11	100S	200E	U-7206	7050	Federal	WD	A
4304731046	RBU 1-10E	NWNE	10	100S	190E	U-013792	7050	Federal	GW	S
4304731115	RBU 16-16F	SESE	16	100S	200E	U-7206	7050	Federal	GW	P
4304731140	RBU 12-18F	NWSW	18	100S	200E	U-013793	7050	Federal	GW	P
4304731141	RBU 3-24E	NENW	24	100S	190E	U-013794	7050	Federal	GW	P
4304731143	RBU 3-23E	NENW	23	100S	190E	U-013766	7050	Federal	GW	P
4304731144	RBU 9-23E	NESE	23	100S	190E	U-013766	7050	Federal	GW	P
4304731145	RBU 9-14E	NESE	14	100S	190E	U-013792	7050	Federal	GW	P
4304731160	RBU 3-15E	NENW	15	100S	190E	U-013766	7050	Federal	GW	P
4304731161	RBU 10-15E	NWSE	15	100S	190E	U-013766	7050	Federal	GW	P
4304731176	RBU 9-10E	NESE	10	100S	190E	U-013792	7050	Federal	GW	P
4304731196	RBU 3-14E	SENE	14	100S	190E	U-013792	7050	Federal	GW	P
4304731252	RBU 8-4E	SENE	04	100S	190E	U-013792	7050	Federal	GW	P
4304731322	RBU 1-19F	NENE	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304731323	RBU 5-10E	SWNW	10	100S	190E	U-013792	7050	Federal	GW	P
4304731369	RBU 3-13E	NENW	13	100S	190E	U-013765	7050	Federal	GW	P
4304731518	RBU 16-3E	SESE	03	100S	190E	U-035316	7050	Federal	GW	P
4304731519	RBU 11-11F	NESW	11	100S	200E	U-7206	7050	Federal	GW	P
4304731520	RBU 1-17F	NENE	17	100S	200E	U-013769-B	7050	Federal	GW	P
4304731605	RBU 9-13E	NESE	13	100S	190E	U-013765	7050	Federal	GW	P
4304731606	RBU 3-22E	NENW	22	100S	190E	U-013792	7050	Federal	GW	P
4304731607	RBU 8-24E	SENE	24	100S	190E	U-013794	7050	Federal	GW	P
4304731608	RBU 15-18F	SWSE	18	100S	200E	U-013794	7050	Federal	GW	P

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304731613	RBW 5-11F	SWNW	11	100S	200E	U-7206	7050	Federal	GW	P
4304731615	RBW 4-22F	NWNW	22	100S	200E	U-0143521-A	7050	Federal	GW	S
4304731652	RBW 6-17E	SWNW	17	100S	190E	U-03535	7050	Federal	GW	P
4304731715	RBW 5-13E	SWNW	13	100S	190E	U-013765	7050	Federal	GW	P
4304731717	RBW 13-13E	SWSW	13	100S	190E	U-013765	7050	Federal	GW	P
4304731739	RBW 9-9E	NESE	09	100S	190E	U-03505	7050	Federal	GW	P
4304732033	RBW 13-14E	SWSW	14	100S	190E	U-013792	7050	Federal	GW	P
4304732037	RBW 11-3E	NESW	03	100S	190E	U-013765	7050	Federal	GW	P
4304732038	RBW 6-18F	SENE	18	100S	200E	U-013769	7050	Federal	GW	P
4304732040	RBW 15-24E	SWSE	24	100S	190E	U-013794	7050	Federal	GW	P
4304732041	RBW 5-14E	SWNW	14	100S	190E	U-013792	7050	Federal	GW	P
4304732050	RBW 12-20F	NWSW	20	100S	200E	U-0143520-A	7050	Federal	GW	P
4304732051	RBW 7-13E	SWNE	13	100S	190E	U-013765	7050	Federal	GW	P
4304732070	RBW 16-19F	SESE	19	100S	200E	U-013769-A	7050	Federal	WD	A
4304732071	RBW 9-22E	NESE	22	100S	190E	U-013792	7050	Federal	GW	P
4304732072	RBW 15-34B	SWSE	34	090S	190E	U-01773	7050	Federal	GW	P
4304732073	RBW 11-15E	NESW	15	100S	190E	U-013766	7050	Federal	GW	P
4304732074	RBW 13-21F	SWSW	21	100S	200E	U-0143520-A	7050	Federal	GW	P
4304732075	RBW 10-22F	NWSE	22	100S	200E	U-01470-A	7050	Federal	GW	P
4304732081	RBW 9-20F	NESE	20	100S	200E	U-0143520-A	7050	Federal	GW	P
4304732082	RBW 15-23E	SWSE	23	100S	190E	U-013766	7050	Federal	GW	P
4304732083	RBW 13-24E	SWSW	24	100S	190E	U-013794	7050	Federal	GW	P
4304732095	RBW 3-21E	NENW	21	100S	190E	U-013766	7050	Federal	GW	P
4304732103	RBW 15-17F	SWSE	17	100S	200E	U-013769-C	7050	Federal	GW	P
4304732105	RBW 13-19F	SWSW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304732107	RBW 1-21E	NENE	21	100S	190E	U-013766	7050	Federal	GW	P
4304732128	RBW 9-21E	NESE	21	100S	190E	U-013766	7050	Federal	GW	P
4304732129	RBW 9-17E	NESE	17	100S	190E	U-03505	7050	Federal	GW	P
4304732133	RBW 13-14F	SWSW	14	100S	200E	U-013793-A	7050	Federal	GW	P
4304732134	RBW 9-11F	NESE	11	100S	200E	U-7206	7050	Federal	GW	P
4304732138	RBW 5-21F	SWNW	21	100S	200E	U-013793	7050	Federal	GW	P
4304732146	RBW 1-20E	NENE	20	100S	190E	U-03505	7050	Federal	GW	P
4304732149	RBW 8-18F	SENE	18	100S	200E	U-013769	7050	Federal	GW	P
4304732153	RBW 13-23E	SWSW	23	100S	190E	U-13766	7050	Federal	GW	P
4304732154	RBW 5-24E	SWNW	24	100S	190E	U-013794	7050	Federal	GW	P
4304732156	RBW 5-14F	SWNW	14	100S	200E	U-013793A	7050	Federal	GW	P
4304732166	RBW 7-15E	SWNE	15	100S	190E	U-013766	7050	Federal	GW	P
4304732167	RBW 15-13E	SWSE	13	100S	190E	U-013765	7050	Federal	GW	P
4304732189	RBW 13-10F	SWSW	10	100S	200E	14-20-H62-2645	7050	Indian	GW	P
4304732190	RBW 15-10E	SWSE	10	100S	190E	U-013792	7050	Federal	GW	P
4304732191	RBW 3-17FX	NENW	17	100S	200E	U-013769-C	7050	Federal	GW	P
4304732197	RBW 13-15E	SWSW	15	100S	190E	U-013766	7050	Federal	GW	P
4304732198	RBW 7-22E	SWNE	22	100S	190E	U-013792	7050	Federal	GW	P
4304732199	RBW 5-23E	SWNW	23	100S	190E	U-013766	7050	Federal	GW	P
4304732201	RBW 13-18F	SWSW	18	100S	200E	U-013793	7050	Federal	GW	S
4304732211	RBW 15-15E	SWSE	15	100S	190E	U-013766	7050	Federal	GW	P

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr_qtr	sec	twp	rng	lease_num	entity	Lease	well	stat
4304732213	RBU 5-19F	SWNW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304732217	RBU 9-17F	NESE	17	100S	200E	U-013769-C	7050	Federal	GW	P
4304732219	RBU 15-14E	SWSE	14	100S	190E	U-013792	7050	Federal	GW	P
4304732220	RBU 5-3E	SWNW	03	100S	190E	U-03505	7050	Federal	GW	P
4304732228	RBU 9-3E	NESE	03	100S	190E	U-035316	7050	Federal	GW	P
4304732239	RBU 7-14E	SWNE	14	100S	190E	U-103792	7050	Federal	GW	P
4304732240	RBU 9-14F	NESE	14	100S	200E	U-013793-A	7050	Federal	GW	P
4304732242	RBU 5-22E	SWNW	22	100S	190E	U-013792	7050	Federal	GW	P
4304732263	RBU 8-13E	SENE	13	100S	190E	U-013765	7050	Federal	GW	P
4304732266	RBU 9-21F	NESE	21	100S	200E	U-0143520-A	7050	Federal	GW	P
4304732267	RBU 5-10F	SWNW	10	100S	200E	U-7206	7050	Federal	GW	P
4304732268	RBU 9-10F	NESE	10	100S	200E	U-7206	7050	Federal	GW	P
4304732269	RBU 4-15F	NWNW	15	100S	200E	INDIAN	7050	Indian	GW	PA
4304732270	RBU 14-22F	SESW	22	100S	200E	U-0143519	7050	Federal	GW	P
4304732276	RBU 5-21E	SWNW	21	100S	190E	U-013766	7050	Federal	GW	P
4304732289	RBU 7-10E	SWNE	10	100S	190E	U-013792	7050	Federal	GW	P
4304732290	RBU 5-17F	SWNW	17	100S	200E	U-013769-C	7050	Federal	GW	P
4304732293	RBU 3-3E	NENW	03	100S	190E	U-013765	7050	Federal	GW	P
4304732295	RBU 13-22E	SWSW	22	100S	190E	U-013792	7050	Federal	GW	P
4304732301	RBU 7-21E	SWNE	21	100S	190E	U-013766	7050	Federal	GW	P
4304732309	RBU 15-21F	SWSE	21	100S	200E	U-0143520-A	7050	Federal	GW	P
4304732310	RBU 15-20F	SWSE	20	100S	200E	U-0143520-A	7050	Federal	GW	P
4304732312	RBU 9-24E	NESE	24	100S	190E	U-013794	7050	Federal	GW	P
4304732313	RBU 3-20F	NENW	20	100S	200E	U-013793-A	7050	Federal	GW	P
4304732315	RBU 11-21F	NESW	21	100S	200E	U-0143520-A	7050	Federal	GW	P
4304732317	RBU 15-22E	SWSE	22	100S	190E	U-013792	7050	Federal	GW	P
4304732328	RBU 3-19FX	NENW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304732331	RBU 2-11F	NWNE	11	100S	200E	U-01790	7050	Federal	GW	P
4304732347	RBU 3-11F	NENW	11	100S	200E	U-7206	7050	Federal	GW	P
4304732391	RBU 2-23F	NWNE	23	100S	200E	U-013793-A	7050	Federal	GW	S
4304732392	RBU 11-14F	NESW	14	100S	200E	U-013793-A	7050	Federal	GW	P
4304732396	RBU 3-21F	NENW	21	100S	200E	U-013793-A	7050	Federal	GW	P
4304732407	RBU 15-14F	SWSE	14	100S	200E	U-013793-A	7050	Federal	GW	P
4304732408	RBU 4-23F	NWNW	23	100S	200E	U-013793-A	7050	Federal	GW	P
4304732415	RBU 3-10EX (RIG SKID)	NENW	10	100S	190E	UTU-035316	7050	Federal	GW	P
4304732483	RBU 5-24EO	SWNW	24	100S	190E	U-013794	11719	Federal	OW	S
4304732512	RBU 8-11F	SENE	11	100S	200E	U-01790	7050	Federal	GW	P
4304732844	RBU 15-15F	SWSE	15	100S	200E	14-20-H62-2646	7050	Indian	GW	P
4304732899	RBU 3-14F	NENW	14	100S	200E	U-013793-A	7050	Federal	GW	P
4304732900	RBU 8-23F	SENE	23	100S	200E	U-013793-A	7050	Federal	GW	P
4304732901	RBU 12-23F	NWSW	23	100S	200E	U-01470-A	7050	Federal	GW	P
4304732902	RBU 1-15F	NENE	15	100S	200E	U-7260	7050	Federal	GW	S
4304732903	RBU 3-15F	NENW	15	100S	200E	U-7260	7050	Federal	GW	P
4304732904	RBU 9-15F	NESE	15	100S	200E	U-7260	7050	Federal	GW	P
4304732934	RBU 3-10F	NENW	10	100S	200E	U-7206	7050	Federal	GW	P
4304732969	RBU 11-10F	NESW	10	100S	200E	U-7206	7050	Federal	GW	P

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304732970	RBU 12-15F	NWSW	15	100S	200E	U-7206	7050	Federal	GW	P
4304732971	RBU 15-16F	SWSE	16	100S	200E	U-7206	7050	Federal	GW	S
4304732972	RBU 1-21F	NENE	21	100S	200E	U-013793-A	7050	Federal	GW	P
4304732989	RBU 13-10E	SWSW	10	100S	190E	U-013792	7050	Federal	GW	P
4304732990	RBU 13-18F2	SWSW	18	100S	200E	U-013793	7050	Federal	GW	P
4304732991	RBU 6-19F	SENW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304733033	RBU 7-23E	NWNE	23	100S	190E	U-013766	7050	Federal	GW	P
4304733034	RBU 9-18F	NESE	18	100S	200E	U-013794	7050	Federal	GW	P
4304733035	RBU 14-19F	SESW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304733087	RBU 6-23F	SENW	23	100S	200E	U-013793-A	7050	Federal	GW	P
4304733088	RBU 1-10F	NENE	10	100S	200E	U-7206	7050	Federal	GW	P
4304733089	RBU 8-22F	SENE	22	100S	200E	U-0143521	7050	Federal	GW	P
4304733090	RBU 11-22F	NESW	22	100S	200E	U-0143519	7050	Federal	GW	P
4304733091	RBU 16-22F	SESE	22	100S	200E	U-01470-A	7050	Federal	GW	P
4304733156	RBU 4-14E	NWNW	14	100S	190E	U-013792	7050	Federal	GW	P
4304733157	RBU 7-19F	SWNE	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304733158	RBU 7-20F	SWNE	20	100S	200E	U-013793-A	7050	Federal	GW	P
4304733159	RBU 7-24E	SWNE	24	100S	190E	U-013794	7050	Federal	GW	P
4304733160	RBU 8-15E	SENE	15	100S	190E	U-013766	7050	Federal	GW	P
4304733161	RBU 16-10E	SESE	10	100S	190E	U-013792	7050	Federal	GW	P
4304733194	RBU 2-14E	NWNE	14	100S	190E	U-013792	7050	Federal	GW	P
4304733272	RBU 13-3F	SWSW	03	100S	200E	U-013767	7050	Federal	GW	P
4304733361	RBU 5-3F	SWNW	03	100S	200E	U-013767	7050	Federal	GW	P
4304733362	RBU 15-10F	SWSE	10	100S	200E	U-7206	7050	Federal	GW	P
4304733363	RBU 5-16F	SWNW	16	100S	200E	U-7206	7050	Federal	GW	P
4304733365	RBU 12-14E	NWSW	14	100S	190E	U-013792	7050	Federal	GW	P
4304733366	RBU 5-18F	SWNW	18	100S	200E	U-013769	7050	Federal	GW	P
4304733367	RBU 10-23F	NWSE	23	100S	200E	U-01470-A	7050	Federal	GW	P
4304733368	RBU 14-23F	SESW	23	100S	200E	U-01470-A	7050	Federal	GW	S
4304733424	RBU 5-20F	SWNW	20	100S	200E	U-013793-A	7050	Federal	GW	P
4304733643	RBU 2-13E	NWNE	13	100S	190E	U-013765	7050	Federal	GW	P
4304733644	RBU 4-13E	NWNW	13	100S	190E	U-013765	7050	Federal	GW	P
4304733714	RBU 4-23E	NWNW	23	100S	190E	U-013766	7050	Federal	GW	P
4304733715	RBU 6-13E	SENW	13	100S	190E	U-013765	7050	Federal	GW	P
4304733716	RBU 10-14E	NWSE	14	100S	190E	U-013792	7050	Federal	GW	P
4304733838	RBU 8-10E	SENE	10	100S	190E	U-013792	7050	Federal	GW	P
4304733839	RBU 12-23E	NWSW	23	100S	190E	U-013766	7050	Federal	GW	P
4304733840	RBU 12-24E	NWSW	24	100S	190E	U-013794	7050	Federal	GW	P
4304733841	RBU 14-23E	SESW	23	100S	190E	U-013766	7050	Federal	GW	P
4304734302	RBU 1-23F	NENE	23	100S	200E	UTU-013793-A	7050	Federal	GW	P
4304734661	RBU 16-15E	SESE	15	100S	190E	U-013766	7050	Federal	GW	P
4304734662	RBU 10-14F	NWSE	14	100S	200E	U-013793-A	7050	Federal	GW	P
4304734663	RBU 6-14E	SENW	14	100S	190E	U-013792	7050	Federal	GW	P
4304734670	RBU 8-23E	NENE	23	100S	190E	U-013766	7050	Federal	GW	P
4304734671	RBU 4-24E	NENE	23	100S	190E	U-013766	7050	Federal	GW	P
4304734701	RBU 12-11F	SENW	11	100S	200E	U-7206	7050	Federal	GW	P

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304734702	RBU 2-15E	NWNE	15	100S	190E	U-013766	7050	Federal	GW	P
4304734703	RBU 4-17F	NWNW	17	100S	200E	U-013769-C	7050	Federal	GW	P
4304734745	RBU 10-20F	NESE	20	100S	200E	U-0143520-A	7050	Federal	GW	P
4304734749	RBU 7-18F	SWNE	18	100S	200E	U-013769	7050	Federal	GW	P
4304734750	RBU 12-10F	SWSW	10	100S	200E	14-20-H62-2645	7050	Indian	GW	P
4304734810	RBU 10-13E	NWSE	13	100S	190E	U-013765	7050	Federal	GW	P
4304734812	RBU 1-24E	NENE	24	100S	190E	U-013794	7050	Federal	GW	P
4304734826	RBU 12-21F	NESE	20	100S	200E	U-0143520-A	7050	Federal	GW	P
4304734828	RBU 4-15E	NWNW	15	100S	190E	U-013766	7050	Federal	GW	P
4304734844	RBU 14-14E	SESW	14	100S	190E	U-013792	7050	Federal	GW	P
4304734845	RBU 10-24E	NWSE	24	100S	190E	U-013794	7050	Federal	GW	P
4304734888	RBU 4-21E	NWNW	21	100S	190E	U-013766	7050	Federal	GW	P
4304734889	RBU 16-24E	SESE	24	100S	190E	U-13794	7050	Federal	GW	P
4304734890	RBU 12-18F2	NWSW	18	100S	200E	U-013793	7050	Federal	GW	P
4304734891	RBU 10-23E	NESW	23	100S	190E	U-013766	7050	Federal	GW	P
4304734892	RBU 8-22E	SENE	22	100S	190E	U-013792	7050	Federal	GW	P
4304734906	RBU 6-22E	SENE	22	100S	190E	U-013792	7050	Federal	GW	P
4304734907	RBU 2-24E	NWNE	24	100S	190E	U-013794	7050	Federal	GW	P
4304734910	RBU 4-16F	NWNW	16	100S	200E	U-7206	7050	Federal	GW	P
4304734911	RBU 12-19F	NWSW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304734912	RBU 14-20F	SESW	20	100S	200E	U-0143520-A	7050	Federal	GW	P
4304734942	RBU 1-22F	NWNW	23	100S	200E	U-013793-A	7050	Federal	GW	P
4304734945	RBU 8-19F	SENE	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304734946	RBU 8-20F	SENE	20	100S	200E	U-013793-A	7050	Federal	GW	P
4304734962	RBU 12-17F	NWSW	17	100S	200E	U-013769-C	7050	Federal	GW	P
4304734963	RBU 2-17F	NWNE	17	100S	200E	U-013769-C	14117	Federal	GW	P
4304734966	RBU 14-18F	SESW	18	100S	200E	U-013793	7050	Federal	GW	P
4304734967	RBU 10-18F	NWSE	18	100S	200E	U-013794	7050	Federal	GW	P
4304734968	RBU 10-19F	NWSE	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304734969	RBU 10-3E	NWSE	03	100S	190E	U-035316	7050	Federal	GW	P
4304734970	RBU 12-3E	NWSW	03	100S	190E	U-013765	7050	Federal	GW	P
4304734971	RBU 15-3E	SWSE	03	100S	190E	U-35316	7050	Federal	GW	P
4304734974	RBU 12-10E	NWSW	10	100S	190E	U-013792	14025	Federal	GW	P
4304734975	RBU 14-10E	NENW	15	100S	190E	U-013766	7050	Federal	GW	P
4304734976	RBU 16-13E	SESE	13	100S	190E	U-013765	7050	Federal	GW	P
4304734977	RBU 8-14E	SENE	14	100S	190E	U-013792	7050	Federal	GW	P
4304734978	RBU 6-15E	SENE	15	100S	190E	U-013766	7050	Federal	GW	P
4304734979	RBU 12-15E	NWSW	15	100S	190E	U-013766	7050	Federal	GW	P
4304734981	RBU 16-17E	SESE	17	100S	190E	U-013766	7050	Federal	GW	P
4304734982	RBU 8-21E	SENE	21	100S	190E	U-013766	7050	Federal	GW	P
4304734983	RBU 4-22E	NWNW	22	100S	190E	U-013792	7050	Federal	GW	P
4304734986	RBU 2-20F	NWNE	20	100S	200E	U-03505	7050	Federal	GW	P
4304734987	RBU 9-20E	SWNW	21	100S	190E	U-03505	7050	Federal	GW	P
4304734989	RBU 7-20E	NENE	20	100S	190E	U-03505	7050	Federal	GW	P
4304734990	RBU 8-20E	SWNW	21	100S	190E	U-03505	14164	Federal	GW	P
4304735041	RBU 16-23E	SWSE	23	100S	190E	U-013766	7050	Federal	GW	P

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304735042	RBU 12-22E	NWSW	22	100S	190E	U-013792	14165	Federal	GW	P
4304735058	RBU 7-23F	SWNE	23	100S	200E	U-013793-A	7050	Federal	GW	P
4304735059	RBU 12-13E	NWSW	13	100S	190E	U-013765	7050	Federal	GW	P
4304735060	RBU 14-13E	SESW	13	100S	190E	U-013765	7050	Federal	GW	P
4304735061	RBU 2-22E	NWNE	22	100S	190E	U-013792	7050	Federal	GW	P
4304735062	RBU 6-24E	SENE	24	100S	190E	U-013794	7050	Federal	GW	P
4304735082	RBU 4-17E	NWNW	17	100S	190E	U-03505	7050	Federal	GW	P
4304735086	RBU 16-14E	NENE	23	100S	190E	U-013792	7050	Federal	GW	P
4304735087	RBU 2-3E	NWNE	03	100S	190E	U-013765	7050	Federal	GW	P
4304735088	RBU 6-3E	SENE	03	100S	190E	U-03505	7050	Federal	GW	P
4304735100	RBU 10-10E	NWSE	10	100S	190E	U-013792	7050	Federal	GW	P
4304735101	RBU 16-22E	SESE	22	100S	190E	U-013792	7050	Federal	GW	P
4304735112	RBU 14-24E	SESW	24	100S	190E	U-013794	7050	Federal	GW	P
4304735129	RBU 6-21F	SENE	21	100S	200E	U-013793-A	7050	Federal	GW	P
4304735170	RBU 1-9E	NESE	09	100S	190E	U-03505	7050	Federal	GW	P
4304735171	RBU 16-9E	NESE	09	100S	190E	U-013765	7050	Federal	GW	P
4304735232	RBU 14-21F	SESW	21	100S	200E	U-0143520	7050	Federal	GW	P
4304735250	RBU 13-19F2	NWSW	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304735251	RBU 15-19F	SWSE	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304735270	RBU 16-21E	SESE	21	100S	190E	U-013766	7050	Federal	GW	P
4304735304	RBU 13-20F	SWSW	20	100S	200E	U-013769	7050	Federal	GW	P
4304735305	RBU 4-21F	NWNW	21	100S	200E	U-013793-A	7050	Federal	GW	P
4304735306	RBU 16-21F	SESE	21	100S	200E	U-0143520-A	7050	Federal	GW	P
4304735468	RBU 15-22F	SWSE	22	100S	200E	U-01470-A	7050	Federal	GW	P
4304735469	RBU 11-23F	SENE	23	100S	200E	U-01470A	7050	Federal	GW	P
4304735549	RBU 1-14F	NENE	14	100S	200E	UTU-013793-A	7050	Federal	GW	P
4304735640	RBU 2-21E	NWNE	21	100S	190E	U-013766	7050	Federal	GW	P
4304735644	RBU 10-17E	NWSE	17	100S	190E	U-013766	7050	Federal	GW	P
4304735645	RBU 12-21E	NWSW	21	100S	190E	U-013766	7050	Federal	GW	P
4304736200	RBU 8-17E	SWNE	17	100S	190E	U-013766	7050	Federal	GW	P
4304736201	RBU 15-17EX	SWSE	17	100S	190E	U-013766	7050	Federal	GW	P
4304736293	RBU 2-10E	NWNE	10	100S	190E	U-013792	7050	Federal	GW	P
4304736294	RBU 6-10E	NENW	10	100S	190E	U-013792	7050	Federal	GW	P
4304736296	RBU 6-21E	SENE	21	100S	190E	U-013766	7050	Federal	GW	P
4304736297	RBU 10-22E	NWSE	22	100S	190E	U-013792	7050	Federal	GW	P
4304736318	RBU 14-22E	SESW	22	100S	190E	U-013792	7050	Federal	GW	P
4304736427	RBU 9-15E	NESE	15	100S	190E	U-013766	7050	Federal	GW	DRL
4304736428	RBU 2-17E	NWNE	17	100S	190E	U-013766	7050	Federal	GW	P
4304736429	RBU 1-17E	NENE	17	100S	190E	U-013766	7050	Federal	GW	DRL
4304736432	RBU 3-19F2	NWNW	19	100S	200E	U-013769-A	15234	Federal	GW	P
4304736433	RBU 14-17F	SESW	17	100S	200E	U-03505	7050	Federal	GW	P
4304736434	RBU 2-19F	NWNE	19	100S	200E	U-013769-A	7050	Federal	GW	P
4304736435	RBU 5-19FX	SWNW	19	100S	200E	U-013769-A	15855	Federal	GW	P
4304736436	RBU 4-20F	NWNW	20	100S	200E	U-013793-A	7050	Federal	GW	P
4304736605	RBU 16-14F	SESE	14	100S	200E	U-013793A	7050	Federal	GW	P
4304736608	RBU 4-3E	NWNW	03	100S	190E	U-035316	7050	Federal	GW	P

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304736609	RBU 8-3E	SENE	03	100S	190E	U-013765	7050	Federal	GW	P
4304736610	RBU 14-3E	SESW	03	100S	190E	U-013765	7050	Federal	GW	P
4304736686	RBU 13-3E	NWSW	03	100S	190E	U-013765	15235	Federal	GW	P
4304736810	RBU 1-3E	NENE	03	100S	190E	U-013765	7050	Federal	GW	DRL
4304736850	RBU 2-10F	NWNE	10	100S	200E	U-7206	7050	Federal	GW	P
4304736851	RBU 8-21F	SENE	21	100S	200E	U-013793-A	7050	Federal	GW	P
4304737033	RBU 4-10E	SWNW	10	100S	190E	U-035316	7050	Federal	GW	P
4304737057	RBU 11-17E	NWSE	17	100S	190E	U-03505	7050	Federal	GW	DRL
4304737058	RBU 3-17E	NENW	17	100S	190E	U-03505	7050	Federal	GW	P
4304737201	RBU 3-23F	NENW	23	100S	200E	U-013793-A	7050	Federal	OW	P
4304737341	RBU 11-20F	NESW	20	100S	200E	U-0143520-A	7050	Federal	GW	P
4304737342	RBU 5-15F	SWNW	15	100S	200E	U-7206	7050	Federal	OW	P
4304737343	RBU 10-16F	NWSE	16	100S	200E	U-7206	7050	Federal	OW	P
4304737344	RBU 9-16F	NESE	16	100S	200E	U-7206	7050	Federal	OW	S
4304737450	RBU 14-17E	SESW	17	100S	190E	U-03505	7050	Federal	GW	P
4304737747	RBU 15-9E	NWNE	16	100S	190E	U-013765	7050	Federal	GW	DRL
4304737893	RBU 9-4EA	SENE	04	100S	190E	U-03505	7050	Federal	GW	P
4304737998	RBU 13-23F	SWSW	23	100S	200E	U-01470-A	7050	Federal	GW	P
4304738181	RBU 12-4E	SWNW	04	100S	190E	U-03576	99999	Federal	GW	DRL
4304738182	RBU 11-4E	SE/4	04	100S	190E	U-03505	99999	Federal	GW	DRL
4304738294	RBU 2-4E	NWNE	04	100S	190E	U-013792	7050	Federal	GW	DRL
4304738295	RBU 5-4E	SWNW	04	100S	190E	U-03576	99999	Federal	GW	DRL
4304738543	RBU 28-18F	NESE	13	100S	190E	U 013793-A	7050	Federal	GW	DRL
4304738548	RBU 32-13E	NESE	13	100S	190E	U-013765	7050	Federal	GW	DRL
4304738555	RBU 27-18F	SWSW	18	100S	200E	U-013793	7050	Federal	GW	DRL
4304738556	RBU 27-18F2	SWSW	18	100S	200E	U-013793	7050	Federal	GW	DRL
4304738557	RBU 30-18F	SWSW	18	100S	200E	U-013793	7050	Federal	GW	P
4304738558	RBU 29-18F	SWSW	18	100S	200E	U-013793	7050	Federal	GW	DRL
4304738595	RBU 31-10E	NENE	15	100S	190E	U-013792	7050	Federal	GW	DRL
4304738596	RBU 17-15E	NENE	15	100S	190E	U-013766	7050	Federal	GW	DRL
4304738780	RBU 8B-17E	SENE	17	100S	190E	U-013766	7050	Federal	GW	DRL

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

RIVER BEND UNIT

api	well_name	qtr_qtr	sec	tpw	rng	lease_num	entity	Lease	well	stat
4304730153	NATURAL 1-2	SENW	02	100S	200E	ML-10716	11377	State	OW	PA
4304730260	RBU 11-16E	NESW	16	100S	190E	ML-13214	7050	State	GW	S
4304730583	RBU 11-36B	NESW	36	090S	190E	ML-22541	99998	State	NA	PA
4304730608	RBU 8-16D	SENE	16	100S	180E	ML-13216	99998	State	NA	PA
4304730760	RBU 11-2F	NESW	02	100S	200E	ML-10716	9966	State	OW	S
4304731740	RBU 1-16E	NENE	16	100S	190E	ML-13214	7050	State	GW	P
4304732026	RBU 16-2F	SESE	02	100S	200E	ML-10716	7050	State	GW	P
4304732042	RBU 9-16E	NESE	16	100S	190E	ML-13214	7050	State	GW	P
4304732108	RBU 14-2F	SESW	02	100S	200E	ML-10716	7050	State	GW	P
4304732136	RBU 8-2F	SENE	02	100S	200E	ML-10716	7050	State	GW	P
4304732137	RBU 5-16E	SWNW	16	100S	190E	ML-13214	7050	State	GW	P
4304732245	RBU 7-16E	SWNE	16	100S	190E	ML-13214	7050	State	GW	PA
4304732250	RBU 13-16E	SWSW	16	100S	190E	ML-13214	7050	State	GW	S
4304732292	RBU 15-16E	SWSE	16	100S	190E	ML-13214	7050	State	GW	PA
4304732314	RBU 10-2F	NWSE	02	100S	200E	ML-10716	7050	State	GW	P
4304732352	RBU 3-16F	NENW	16	100S	200E	ML-3393-A	7050	State	GW	P
4304733360	RBU 1-16F	NENE	16	100S	200E	ML-3393	7050	State	GW	P
4304734061	RBU 6-16E	SWNE	16	100S	190E	ML-13214	7050	State	GW	P
4304734167	RBU 1-2F	NENE	02	100S	200E	ML-10716		State	GW	LA
4304734315	STATE 11-2D	NESW	02	100S	180E	ML-26968		State	GW	LA
4304734903	RBU 14-16E	SWSW	16	100S	190E	ML-13214	7050	State	D	PA
4304735020	RBU 8-16E	SENE	16	100S	190E	ML-13214	7050	State	GW	P
4304735021	RBU 10-16E	SWSE	16	100S	190E	ML-13214	7050	State	GW	P
4304735022	RBU 12-16E	NESW	16	100S	190E	ML-13214	7050	State	GW	P
4304735023	RBU 16-16E	SWSW	15	100S	190E	ML-13214	7050	State	GW	P
4304735033	RBU 2-16E	NWNE	16	100S	190E	ML-13214	7050	State	GW	P
4304735081	RBU 15-2F	SWSE	02	100S	200E	ML-10716	7050	State	GW	P
4304735348	RBU 13-16F	NWNW	21	100S	200E	ML-3394	7050	State	GW	DRL
4304736169	RBU 4-16E	NENW	16	100S	190E	ML-13214	7050	State	GW	P
4304736170	RBU 3-16E	NENW	16	100S	190E	ML-13214	7050	State	GW	P



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155



IN REPLY REFER TO
3180
UT-922

Dominion Exploration & Production, Inc.
Attn: James D. Abercrombie
14000 Quail Springs Parkway, #600
Oklahoma City, OK 73134-2600

August 10, 2007

Re: River Bend Unit
Uintah County, Utah

Gentlemen:

On August 8, 2007, we received an indenture dated June 30, 2007, whereby Dominion Exploration & Production, Inc. resigned as Unit Operator and XTO Energy Inc. was designated as Successor Unit Operator for the River Bend Unit, Uintah County, Utah.

This indenture was executed by all required parties and the signatory parties have complied with Sections 5 and 6 of the unit agreement. The instrument is hereby approved effective August 15, 2007. In approving this designation, the Authorized Officer neither warrants nor certifies that the designated party has obtained all required approval that would entitle it to conduct operations under the River Bend Unit Agreement.

Your statewide oil and gas bond No. UTB000138 will be used to cover all operations within the River Bend Unit.

It is requested that you notify all interested parties of the change in unit operator. Copies of the approved instruments are being distributed to the appropriate federal offices, with one copy returned herewith.

Sincerely,

/s/ Greg J. Noble

Greg J. Noble
Acting Chief, Branch of Fluid Minerals

Enclosure

RECEIVED
AUG 16 2007
DIV. OF OIL, GAS & MINING